

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-21132-00-00
Spot: NWNW Sec/Twnshp/Rge: 8-16S-7W
500 feet from N Section Line, 600 feet from W Section Line
Lease Name: SNEATH Well #: 1-8
County: ELLSWORTH Total Vertical Depth: 2190 feet

Operator License No.: 3842
Op Name: LARSON ENGINEERING INC DBA LARS
Address: 562 WEST HIGHWAY 4
OLMITZ, KS 67564

SURF Size: 8.625 feet: 271 175 SX CMT

18
71

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 08/08/2004 4:00 PM
Plug Co. License No.: 30141 Plug Co. Name: SUMMIT DRILLING COMPANY
Proposal Rcvd. from: DAN COX Company: SUMMIT DRILLING COMPANY Phone: (620) 343-3278

Proposed Plugging Method: See actual report.

RECEIVED
KCC DISTRICT #2
OCT 14 2004

WICHITA, KS

Plugging Proposal Received By: _____ WitnessType: NONE
Date/Time Plugging Completed: 08/08/2004 5:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Perfs:

Pumped 35 sacks of cement through drill pipe at 850'. Pulled drill pipe to 550' and pumped 35 sacks of cement. Pulled drill pipe to 320' and pumped 35 sacks of cement. Pulled drill pipe to 40' and pumped 25 sacks of cement to surface. Topped off with 10 sacks of cement.

60/40 posmix with 4% gel.

RECEIVED
KANSAS CORPORATION COMMISSION
OCT 19 2004
CONSERVATION DIVISION
WICHITA, KS

Remarks:

Plugged through: DP

District: 02

Signed Virgil Clothier
(TECHNICIAN)

INVOICED

DATE 10-19-04

TRV. NO. 2005060675

a