

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-20264-00-00
Spot: SWSNWSE Sec/Twnshp/Rge: 16-14S-10W
3640 feet from N Section Line, 1820 feet from E Section Line
Lease Name: BULTMAN Well #: 1
County: ELLSWORTH Total Vertical Depth: 2985 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 SOUTH MAIN STE 200
WICHITA, KS 67202

PROD Size: 5.5 feet: 2980 100 SX CMT
SURF Size: 8.625 feet: 264 165 SX CMT

97⁰¹

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/06/2004 2:00 PM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: FRANK BIEKER Company: TRANS PACIFIC OIL CORPORATIO Phone: (785) 658-7258

Proposed Plugging Method: See actual report.

RECEIVED
KCC DISTRICT #2
OCT 14 2004
WICHITA, KS

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/06/2004 3:20 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Sanded perforations to 2825' and put 5 sacks cement on top. Perforated at 1250', 900', and 315'. Ran tubing to 1250' and pumped 35 sacks of cement. Pulled tubing to 900' and pumped 35 sacks of cement. Pulled tubing to 315' and circulated cement to surface.

Topped off on 10/12/2004 with 38 sacks of cement, Swift Services #7223.

Swift Services #7218
Perf Tech #3022

60/40 posmix with 4% gel.

Perfs:

Top	Bot	Thru	Comments
2860	2888		

RECEIVED
KANSAS CORPORATION COMMISSION
OCT 19 2004
CONSERVATION DIVISION
WICHITA, KS

Remarks:

Plugged through: TBG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

INVOICE
DATE 10-19-04
BY 20050606 77