

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-20042-00-00
Spot: SWNESW Sec/Twnshp/Rge: 20-14S-10W
1650 feet from S Section Line, 1650 feet from W Section Line
Lease Name: BORELL B2 Well #: 3
County: ELLSWORTH Total Vertical Depth: 2510 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 SOUTH MAIN STE 200
WICHITA, KS 67202

PROD Size: 4.5 feet: 2510 60 SX CMT
SURF Size: 8.625 feet: 264 225 SX CMT

\$ 81⁵⁸

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/05/2004 9:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: FRANK BIEKER Company: TRANS PACIFIC OIL CORPORATIO Phone: (785) 658-7258

Proposed Plugging Method: Sand perfs to 2370' & put 4 sxs cement on top; perf at 1250', 850', & 315'. Run tubing to 1250' & pump 35 sxs; pull tubing to 850' & pump 35 sxs; pull tubing to 315' & circ to surf.

RECEIVED
KCC DISTRICT #2
OCT 14 2004

WICHITA, KS

Plugging Proposal Received By: MICHAEL WILSON WitnessType: NONE
Date/Time Plugging Completed: 10/05/2004 12:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Sanded perforations to 2300' and put 4 sacks of cement on top. Perforated at 1250', 850', and 315'. Ran tubing to 1250' and pumped 35 sacks of cement. Pulled tubing to 850' and pumped 35 sacks of cement. Pulled tubing to 315' and circulated cement to surface.

Topped off on 10/14/2004, Ellsworth RediMix #36464

Swift Services #7215
Perf Tech #3019

60/40 posmix with 4% gel.

Perfs:

Top	Bot	Thru	Comments
2418	2422		

RECEIVED
KANSAS CORPORATION COMMISSION
OCT 19 2004
CONSERVATION DIVISION
WICHITA, KS

Remarks:
Plugged through: TBG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

INVOICED
DATE 10-19-04
INV. NO. 2005060677