

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-20104-00-00
Spot: SENWNE Sec/Twnshp/Rge: 20-14S-10W
990 feet from N Section Line, 1650 feet from E Section Line
Lease Name: PEKAREK Well #: 5
County: ELLSWORTH Total Vertical Depth: 2895 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 SOUTH MAIN STE 200
WICHITA, KS 67202

PROD Size: 5.5 feet: 2894 150 SX CMT
SURF Size: 8.625 feet: 491 320 SX CMT

#94⁰⁹

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/06/2004 9:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: FRANK BIEKA Company: TRANS PACIFIC OIL CORPORATIO Phone: (785) 658-7258

Proposed Sand off perfs to 2745' & put 5 sxs cement on top; perf @ 1250', 850' & 540'. Run tubing to 1250' & pump 35 sxs; pull
Plugging tubing to 850' & pump 35 sxs; pull tubing to 540' & circ to surf.
Method:

RECEIVED
KCC DISTRICT #2
OCT 14 2004

Plugging Proposal Received By: MICHAEL WILSON WitnessType: PARTIAL
Date/Time Plugging Completed: 10/06/2004 11:00 AM KCC Agent: VIRGIL CLOTHIER

WICHITA, KS

Actual Plugging Report:

Sanded perforations to 2745' and put 5 sacks of cement on top. Perforated at 1250', 850', and 540'. Ran tubing to 1250' and pumped 35 sacks of cement. Pulled tubing to 850' and pumped 35 sacks of cement. Pulled tubing to 540' and circulated cement to surface.

10/14/2004 -- Topped off, Ellsworth RediMix #36464

Swift Services #7217
Perf Tech #3021

60/40 posmix with 4% gel.

Perfs:

Top	Bot	Thru	Comments
2824	2834		

RECEIVED
KANSAS CORPORATION COMMISSION
OCT 19 2004
CONSERVATION DIVISION
WICHITA, KS

Remarks:

Plugged through: TBG

District: 02

Signed

Virgil Clothier
(TECHNICIAN)

INVOICED

DATE 10-19-04
INV. NO. 2005060677