

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-053-20030-00-00  
Spot: NWNWSW Sec/Twnshp/Rge: 20-14S-10W  
2310 feet from S Section Line, 4950 feet from E Section Line  
Lease Name: ST WENCELAUS CHURCH Well #: 1  
County: ELLSWORTH Total Vertical Depth: 2956 feet

Operator License No.: 9408  
Op Name: TRANS PACIFIC OIL CORPORATION  
Address: 100 SOUTH MAIN STE 200  
WICHITA, KS 67202

PROD Size: 4.5 feet: 2956 50 SX CMT  
SURF Size: 8.625 feet: 266 225 SX CMT

# 96<sup>07</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/05/2004 1:00 PM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: FRANK BIEKER Company: TRANS PACIFIC OIL CORPORATIO Phone: (785) 658-7258

Proposed Plugging Method: See actual report.

RECEIVED  
KCC DISTRICT #2  
OCT 14 2004  
WICHITA, KS

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: NONE  
Date/Time Plugging Completed: 10/05/2004 5:20 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Sanded perforations to 1590' and put 4 sacks of cement on top. Perforated at 1250', 850', and 315'. Ran tubing to 1250' and pumped 35 sacks of cement. Pulled tubing to 850' and pumped 35 sacks of cement. Pulled tubing to 315' and circulated cement to surface.

Topped off on 10/12/2004, Used approximately 28 sacks of cement; Swift Services #7223

Swift Services #7216  
Perf Tech #3020

60/40 posmix with 4% gel.

Perfs:

| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 2880 | 2888 |      |          |
| 2820 | 2830 |      |          |

RECEIVED  
KANSAS CORPORATION COMMISSION  
OCT 19 2004  
CONSERVATION DIVISION  
WICHITA, KS

Remarks:

Plugged through: TBG

District: 02

Signed

Virgil Clothier  
(TECHNICIAN)

INVOICED

DATE

10-19-04

INV. NO.

2005060677