

15-147-00950-00-00

10-31 4-032020

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- - 1960

SE /4 SEC. 25, 04 S, 20 W
1980 feet from S section line
330 feet from E section line

Operator license# 5447

Lease Slinker Unit well # 204

Operator: OXY USA, Inc.

County Phillips

Address: 110 S. Main
Suite #800
Wichita, Kansas 67202

Well total depth 3486 feet ^{113.30}
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 157 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Halliburton License# -

Address: Oberlin, Kansas

Company to plug at: Hour: A.M. Day: 31 Month: October Year: 94

Plugging proposal received from: Jim Newell

Company: OXY USA, Inc. Phone:

Were: Order 225 sxs. 60/40 pozmix - 10% gel - 500# hulls.
12 sxs. gel - 1/4# flocele.

RECEIVED
KANSAS CORPORATION COMMISSION

NOV 7 0 1994

11-10-94
CONSERVATION DIVISION
WICHITA [KS]

Plugging Proposal Received by: Carl Goodrow
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 9:30A.M., Day: 31, Month: October, Year: 94

Actual plugging report: 8 5/8" set @ 157' w/125 sxs. cwc. 5 1/2" set @
3270' w/150 sxs. P.B.T.D. 3234'. Prod. perms. 3135' - 3211'. Critical
area control shots at 920' and 1525'. Squeezed 5 1/2" w/50 sxs. cement
blend followed w/12 sxs. gel, followed w/125 sxs. cement blend w/450#
hulls mixed in to Max. P.S.I. 400#. Close in P.S.I. 100#. Squeezed
8 5/8" w/50 sxs. cement blend w/50# hulls to Max. P.S.I. 350#. Close
in P.S.I. 300#. Plug complete.

Remarks:

Condition of casing(in hole): GOOD X BAD Anhy.plug: YES X NO
Bottom plug(in place): YES , CALC X, NO Dakota plug: YES X, NO
Plugged through TUBING , CASING X. Elevation: GL

I did X observe the plugging.

Carl Goodrow

(agent)

Form CP-2/3

INVOICED

DATE 11-18-94

INV. NO. 41723