

To: 6 010629
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

15-147-19101-00-01 329
API NUMBER 15- 1-20-60

NE NW SE, SEC. 25, T 4 S, R 20 W/E
2310 feet from S section line
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5447
Operator: Oxy USA Inc.
Name & Address: 3545 NW 58th St.
Oklahoma City, Ok. 73112

Lease Name Slinker Unit Well # 203 W Inj.
County Phillips 112.94
Well Total Depth 3475' PB 3257 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 165

Abandoned Oil Well Gas Well Input Well SWD Well U&A
Other well as hereinafter indicated

Plugging Contractor Oxy License Number
Address Same

Company to plug at: Hour: 9:00AM Day: 16 Month: August Year: 19 88

Plugging proposal received from Gene Hutchinson
(company name) Oxy (phone)

were: Ran wireline to 3145' - 5 1/2" casing at 3281' perf at 3121' - 3218'.
Elev. 1980'. Top Dakota SLD 1400'. Perf at 760'. Perf anhydrite at 1488'.
D.V. at 1507' w/100 sks. Order 400 sks 60/40 Poz 8% Gel 100# Flocele 400#
Hulls 50 sks Common Cement.

Plugging Proposal Received by D.F.B.
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 10:30PMDay: 16 Month: August Year: 19 88

ACTUAL PLUGGING REPORT Pumped down 5 1/2" casing 50 sks Common Cement.

Then, 50 sks 60/40. Then, 130 sks 60/40 Poz w/200# Hulls. Max pressure 600# Holding 500#.
Pumped down 8 5/8" 120 sks 60/40 w/200# Hulls. Max pressure 500#. Holding 300#.

RECEIVED
SEP - 1 1988
09-01-88
CONSERVATION DIVISION
Wichita, Kansas

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED
Please observe this plugging.

Signed Dale F. Balthazor
(TECHNICIAN)
Dale F. Balthazor

DATE 9-8-88
INV. NO. 22152
8-16