

10-5-88 15-137-00587-00500 R

To: 6 041019
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 1-1954

C N/2 NE, SEC. 2, T. 4 S, R. 24 ~~W. 24~~

4620 feet from S section line

1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5135

Lease Name Schoen B Well # 2

Operator: John O. Farmer Inc.
Name & Address: Box 352
Russell, Ks. 67665

County Norton 123.40

Well Total Depth 3797 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8" w/125

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ U&A _____

Other well as hereinafter indicated _____

Plugging Contractor Allied Cement License Number _____

Address Russell, Ks.

Company to plug at: Hour: 1:30PM Day: 5 Month: 10 Year: 19 88

Plugging proposal received from Lawrence Slim Eichman

(company name) J.O. Farmer (phone) _____

were: 5 1/2" casing set at 3793' w/75 sks. Top perf at 3793' - 97'.

Perf anhy at 2045' and base Dakota at 1275'.

Ordered 400 sks 60/40 Poz 8% Gel w/1/4" F.C. plus 6 sks Hulls.

Plugging Proposal Received by Dennis L. Hamel (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: _____ Day: 5 Month: Oct Year: 19 88

ACTUAL PLUGGING REPORT Pumped in 5 1/2" casing 325 sks cement w/1/4" F.C. plus 5 sks Hulls

mixed in cement. Max 700# S.I. 300# psi. Pumped in 8 5/8" casing 75 sks cmeent w/1/4" F.C.

plug 1 sk Hulls mixed in cement. Max 300# S.I. 200# psi.

RECEIVED STATE CORPORATION COMMISSION

MAR 07 1989 03-07-1989 CONSERVATION DIVISION Kansas

Remarks: (If additional description is necessary, use BACK of THIS form.)

INVOICED observe this plugging.

DATE 3-7-89

INV. NO. 24074

rls

Signed Dennis L. Hamel (TECHNICIAN)