

10-5-88 15-137-00586-00-ops 8
1-1954

6 041018

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-
NE NE NE, SEC. 2, T 4 S, R 24 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5135

Operator: John O. Farmer Inc.
Name & Address: Box 352
Russell, Ks. 67665

4950 feet from S section line
330 feet from E section line

Lease Name Schoen B Well # 1

County Norton 123.57

Well Total Depth 3802 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 290' w/125

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Allied Cementing License Number

Address Russell, Ks.

Company to plug at: Hour: 11:00 AM Day: 5 Month: Oct Year: 19 88

Plugging proposal received from L. Slim Eichman

(company name) J.O. Farmer (phone)

were: 5 1/2" casing set at 3799' w/75 sks. Top perf at 3799' - 3802'.

Perf anhy at 2045' and base Dakota at 1275'.

Ordered 400 sks 60/40 Poz 8% Gel w/1/4# F.C. plus 6 sks Hulls.

Plugging Proposal Received by Dennis L. Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:00AM Day: 5 Month: Oct Year: 19 88

ACTUAL PLUGGING REPORT Pumped in 5 1/2" casing 325 sks cement w/1/4# F.C. plus

5 sks Hulls mixed in cement. Max 800#. S.I. 400# psi. Pumped in 8 5/8" casing 75 sks
cement w/1/4# F.C. plus 1 sk Hulls mixed in cement. Max 300# S.I. 200# psi.

RECEIVED
STATE CORPORATION COMMISSION
03-07-1989
MAR 07 1989

Remarks: (If additional description is necessary, use BACK of THIS FORM)

INVOICED (XXXX did not) observe this plugging.

DATE 3-7-89
INV. NO. 24076

Gil S.

Signed Dennis L. Hamel
(TECHNICIAN)
Dennis L. Hamel