

15-137-00755-00-00

To: **6 031538**
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 1953

N/2 NE, SEC. 1, T 4 S, R 24 W/EX
4620 feet from S section line
1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5552
Operator: Gore Oil Co.
Name & Address: Box 2757
Wichita, Ks. 67201-2757

Lease Name Scott Well # 2
County Norton 123.79
Well Total Depth 3809 feet
Conductor Pipe: Size 8 5/8 feet 241
Surface Casing: Size 8 5/8 feet 241

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor B. J. Services License Number _____
Address Hays, Ks.

Company to plug at: Hour: _____ AM Day: 3 Month: May Year: 19 91
Scott

Plugging proposal received from _____
(company name) Gore (phone) _____

were: 8 5/8 set at 241 w/125 sks. 5 1/2 set at 3806 w/100 sks. O.H. 3806 - 3809.
Order 400 sks 65/35 poz 10% gel. 400 lbs. 13 sks gel. B. J. Services
Webb and Gore water trucks.
Wireline to t.d. hole open. Shots in 5 1/2 at 2050 and 1275.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:20AM Day: 3 Month: May Year: 19 91

ACTUAL PLUGGING REPORT Sq 5 1/2 w/100 sks cement blend w/200 lbs. hulls.
Mixed in, followed w/13 sks gel in 40 bbl gel water, followed w/200 sks
cement blend w/100 lbs. hulls mixed into max psi 800 lbs. Close in psi
600 lbs. Sq 8 5/8 w/100lbs. hulls mixed into max psi 300 lbs. Close in
psi 300 lbs. Plug complete.

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 6-17-91

INV. NO. 32155

J.S.

Signed Carl Goodrow
Carl Goodrow, TECHNICIAN, CONSERVATION DIVISION
Wichita, Kansas

RECEIVED
STATE CORPORATION COMMISSION
06-07-1991
JUN 07 1991