

4-041713

15-137-0052A-00-00

8-29

API Number: 15- - 08-24-53

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

NE NE NW /4 SEC. 01, 04 S, 24 W
330 feet from N section line
2310 feet from W section line

Operator license# 5135

Lease: Green Well # 1

Operator: John O. Farmer, Inc.

County: Norton

Address: P.O. Box 352
Russell, Kansas 67665

Well total depth 3812 123.89 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 255 feet
W/125 sxs.

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 9:00 A.M. Day: 29 Month: August Year 1995

Plugging proposal received from: Duane Eichman

Company: John O. Farmer, Inc. Phone:

Were: 5 1/2" casing set at 3805' w/75 sxs cement. O.H. at 3805' - 3812'.
Perf Anhy at 2080' - Dakota at 990' - W.L.M. 3812' - T.O.F. at 2000'.
Ordered 300 sxs. 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls.

RECEIVED
STATE CORPORATION COMMISSION

SEP 15 1995

09-15-1995
WICHITA, KANSAS

Plugging Proposal Received by: Dennis L. Hamel
Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 12:00 P.M., Day: 29, Month: August, Year: 1995

Actual plugging report: Pumped down 5 1/2" casing with 260 sxs cement with 400# hulls. Max. P.S.I. 1200#. S.I.P. 300#. Pumped down 8 5/8" S.P. with 40 sxs cement with 100# hulls. Max. P.S.I. 300#. S.I.P. 200#.

Remarks: Condition of casing(in hole): GOOD X BAD Anhy.plug: YES X NO
Bottom plug(in place): YES X, CALC, NO Dakota plug: YES X, NO
Plugged through TUBING, CASING X. Elevation: GL

I did/did not observe the plugging.

Dennis L. Hamel
(agent)

Form CP-2/3

INVOICED
DATE SEP 22 1995
INV. NO. 13563