

6 031539

S-3

15-137-00080-00-0085

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 1953  
NW NW NE, SEC. 1, T 4 S, R 24 W/E

4950 feet from S section line  
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5552

Lease Name Scott Well # 1  
County Norton 123.82

Operator: Gore Oil Company  
Name & Address: P.O. Box 2757  
Wichita, Kansas 67201-2757

Well Total Depth 3810 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 256

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor B J Services License Number \_\_\_\_\_

Address Hays, Kansas

Company to plug at: Hour: \_\_\_\_\_ P.M. Day: 3 Month: 5 Year: 19 91

Plugging proposal received from Scott

(company name) Gore (phone) \_\_\_\_\_

were: 8 5/8 set @ 256' w/135 sx. 5 1/2 set @ 3804' w/100 sx. OH 3804'-10'  
Order 400 sx. 65/35 poz. 10% Gel. 400# Hulls. 13 sx. Gel. B.J. Services  
Webb and Gore water trucks.

Ran wireline to TD hole open shots @ 2050 and 1275 in 5 1/2

Plugging Proposal Received by Carl Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part  None \_\_\_\_\_

Operations Completed: Hour: 12:05 P.M. Day: 3 Month: 5 Year: 19 91

ACTUAL PLUGGING REPORT Squeezed 5 1/2 w/100 sx. Cement Blend w/200# Hulls.

Mixed in followed with 13 sx. Gel. Followed with 200 sx. Cement Blend w/100# Hulls  
mixed in to max PSI 800# Close in PSI 700#. Squeezed 8 5/8 w/100 sx. Cement  
Blend w/100# Hulls mixed in to max PSI 250#. Close in PSI 250#. Plug complete.

RECEIVED  
STATE CORPORATION COMMISSION  
05-20-1991  
MAY 20 1991

Remarks: \_\_\_\_\_  
(If additional description is necessary, use BACK of this form.)

**INVOLCED**  
observe this plugging.

DATE 5-29-91  
WEL. NO. 31940

*John S.*

Signed Carl Goodrow  
(TECHNICIAN)

CONSERVATION DIVISION  
Wichita, Kansas