

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-21835-00-02
Spot: NENWSE Sec/Twnshp/Rge: 28-33S-5E
2310 feet from S Section Line, 1650 feet from E Section Line
Lease Name: GROSE THOMPSON Well #: 1
County: COWLEY Total Vertical Depth: 3215 feet

Operator License No.: 6679
Op Name: SHORT, W.D. AND MARJORIE D/B/A SH
Address: PO BOX 1
OXFORD, KS 67119

PROD Size: 4.5 feet: 3215 100 SX CMT
SURF Size: 8.625 feet: 205 125 SX CMT

#10449

Well Type: SWD UIC Docket No: D21733.0 Date/Time to Plug: 05/04/2004 8:00 AM
Plug Co. License No.: 6679 Plug Co. Name: SHORT, W.D. AND MARJORIE D/B/A SHORT, W. D. OIL CO.
Proposal Rcvd. from: DON SHORT Company: W. D. SHORT OIL CO. Phone: (620) 455-3576

Proposed Plugging Method: PER KCC RULES & REGULATIONS. SAND TO 1898', 5 SX CMT. SHOOT OFF & PULL CASING, CEMENT FROM 250' TO SURFACE.

RECEIVED
KCC DISTRICT #2
OCT 11 2004

Plugging Proposal Received By: WitnessType: NONE WICHITA, KS
Date/Time Plugging Completed: 05/06/2004 5:00 PM KCC Agent: DONALD HOBERECHT

Actual Plugging Report:

Sanded to 1898' and topped with 5 sacks of cement. Shot off casing at 1352' and pulled casing. Ran tubing to 250' and circulated cement to surface. Topped off with 4 sacks of cement the following day.

127 sacks of 60/40 posmix with 4% gel.

Perfs:

Top	Bot	Thru	Comments
2004	2034		
1948	1968		


RECEIVED
KANSAS CORPORATION COMMISSION
OCT 19 2004
CONSERVATION DIVISION
WICHITA, KS

Remarks:

Plugged through: TBG

District: 02

Signed



(TECHNICIAN)

INVOICED

DATE 10-19-04

INV. NO. 2005060676