

10-5-88 15-137-00592-00700
6-1954

6 041017

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-
C NE, SEC. 2, T 4 S, R 24 W/E
3960 feet from S section line
1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5135

Operator: John O. Farmer Inc.
Name & Address: Box 352
Russell, Ks. 67665

Lease Name Schoen B Well # 4
County Norton
Well Total Depth 3799 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 280' w/125 sks

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ U&A _____

Other well as hereinafter indicated _____

Plugging Contractor Allied Cementing License Number _____

Address Russell, Ks.

Company to plug at: Hour: 3:30PM Day: 5 Month: Oct. Year: 19 88

Plugging proposal received from Lawrence Slim Eichman

(company name) J. O. Farmer (phone) _____

were: 5 1/2" casing set at 3796' w/75 sks. Top perf at 3796' - 99'.

Perf anhy at 2045' and base Dakota at 1275'. Ttbing and rods at 2500'.

Ordered 400 sks 60/40 Poz 8% Gel w/1/4# F.C- plus 6 sks Hulls.

Plugging Proposal Received by Dennis L. Hamel (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 3:30 PM Day: 5 Month: Oct Year: 19 88

ACTUAL PLUGGING REPORT

Pumped in 5 1/2" casing 275 sks cement w/1/4# F.C. plus 2 sks Hulls mixed in cement. Max 500#. S.I. 300# psi. Pumped in 8 5/8" casing 125 sks cement

w/1/4# F.C. plus 2 sks Hulls mixed in cement. Max 300# S.I. 200# psi.

RECEIVED
STATE CORPORATION COMMISSION

MAR 07 1989
03-07-1989
CONSERVATION DIVISION
Wichita, Kansas

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED
serve this plugging.

DATE 3-7-89
INV. NO. 24075

Signed Dennis L. Hamel (TECHNICIAN)