

15-039-00559-00-00

6 031422

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 1951
NE NE SW, SEC. 25, T 4 S, R 27 W/E xx

TECHNICIAN'S PLUGGING REPORT

Operator License # 5011

2310 feet from S section line
2970 feet from E section line

Operator: Viking Res. Inc.
Name & Address 105 S. Broadway Suite 1040
Wichita, Ks. 67202-4224

Lease Name Jennings Unit Well # 4-1
County Decatur 122.85
Well Total Depth 3780 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 350

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050
Address Chase, Ks.

Company to plug at: Hour: AM Day: 1 Month: August Year: 19 90

Plugging proposal received from Vernon
(company name) Kelso (phone) _____

were: 8 5/8 set at 350 w/225 sks. 5 1/2 set at 3550 w/225 sks. Perfs 3028 - 3518.

PBTD 3519. Order sand and common cement. Pull pipe. Order 300 sks 65/35 poz 8% gel.

500 lb. hulls. Allied Cement Co. LaRue Water Truck. Ran wireline to fish, hole open.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:45PM Day: 1 Month: August Year: 19 90

ACTUAL PLUGGING REPORT Sand back to 2975 w/5 sks common cement on sand w/bailer.

Recovered 1000 of casing rom shots at 2000 1600 1400 1200 1000. Sq 8 5/8 w/250 sks. Cement

blend w/500 lbs. hulls mixed into max psi 1500 lbs. Close in psi 300 lbs. Plug complete.

RECEIVED
STATE CORPORATION COMMISSION
10-3-90
OCT 3 1990

Remarks: _____
(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
Wichita, Kansas

INVOICED

DATE 10-5-90

INV. NO. 29553

Handwritten initials

Signed Carl Goodrow
(TECHNICIAN)

Carl Goodrow