

9-1215-039-00538-00-00

6 031424

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 1953

NW SW SE, SEC. 25, T 4 S, R 27 W/E
990 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5011

Lease Name Jennings Unit Well # 5-2

Operator: Viking Res. Inc.
Name & Address: 105 S. Broadway Suite 1040
Wichita, Ks. 67202-4224

County Decatur 116.35

Well Total Depth 3580 feet

Conductor Pipe: Size feet

Surface Casing: Size 10 3/4 feet 687

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Chase, Ks.

Company to plug at: Hour: AM Day: 12 Month: Sept Year: 19 90

Plugging proposal received from Millard

(company name) Kelso (phone)

were: 10 3/4 set at 687 w/325 sks cwc 7" set at 3580 w/175 sks. PBDT 3578.

Perf 3086 - 3577. Order sand and common cement. Pull pipe. Order 250 sks.

65/35 poz 10% gel, 500 lbs. hulls. Allied Cement Co. LaRue Water Trucks.

Kelso Wireline to fish through Black Magic.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:30AM Day: 12 Month: Sept Year: 19 90

ACTUAL PLUGGING REPORT Sand bottom back 3030 w/7 sks common cement on sand w/

bailer. Recovered 1100 of 7" casing. Shots start 2000. Squeezed 10 3/4 w/125 sks cement b

blend w/300 lbs. hulls mixed into max psi 900 lbs. Close in psi 900 lbs. Blew off head. Plug complete.

RECEIVED STATE CORPORATION COMMISSION

Remarks: (If additional description is necessary, use BACK of this form.)

SEP 26 1990

9-26-90

INVOICED (do not observe this plugging.)

CONSERVATION DIVISION Wichita, Kansas

Signed Carl Goodrow (TECHNICIAN)

DATE 10-2-90

INV. NO. 29494

Carl Goodrow