

15-039-00216-00-00

6 031421

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 1953
NE SW SW, SEC. 25, T 4, S, R 27 W/E^{xx}

TECHNICIAN'S PLUGGING REPORT

Operator License # 5011

Operator: Viking Res. Inc.
Name & Address: 105 S. Broadway Suite 1040
Wichita, Ks. 67202-4224

990 feet from S section line
4290 feet from E section line

Lease Name Jennings Unit Well # 4-4

County Decatur 116.12

Well Total Depth 3573 feet

Conductor Pipe: Size feet

Surface Casing: Size 10 3/4 feet 709

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Chase, Ks.

Company to plug at: Hour: PM Day: 1 Month: August Year: 19 90

Plugging proposal received from Vernon

(company name) Kelso (phone)

were: 10 3/4 set at 709 w/625 sks. 7' set at 3567 w/200 sks. PBD 3573.

perfs 3223 - 3573. Order sand and common cement. Pull pipe. Order 300 sks 65/35 poz

8% gel 500 lbs. hulls. Allied Cement Co. LaRue Water Trucks.

Ran Kelso wireline to anhydrite.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 12:00 PM Day: 1 Month: August Year: 19 90

ACTUAL PLUGGING REPORT Sand back to 3173 to 3173 w/6 sks common cement on sand w/bailer

Recovered 1100 casing w/4 shots. Sq 10 3/4 w/250 sks cement blend w/500 lbs. hulls mixed into max psi 400 lbs. Close in psi 200 lb.s Plug complete.

RECEIVED STATE CORPORATION COMMISSION

OCT 3 1990

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 10-5-90

INV. NO. 29552

gib.S.

Signed Carl Goodrow (TECHNICIAN)

Carl Goodrow