

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-147-00905-00-00  
Spot: CSESESW Sec/Twnshp/Rge: 25-4S-20W  
330 feet from S Section Line, 2970 feet from E Section Line  
Lease/Unit Name: SLINKER Well Number: 301  
County: PHILLIPS Total Vertical Depth: 3340 feet

Operator License No.: 31763  
Op Name: BLAKE PRODUCTION CO., INC.  
Address: 3535 NW 58TH ST., STE 1020  
OKLAHOMA CITY, OK 73112

Conductor Pipe: Size feet: 108.55  
Surface Casing: Size 8.625 feet: 220 250 sxs  
Production: Size 5.5 feet: 3339 125 sxs  
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 06/25/2002 9:00 AM  
Plug Co. License No.: 31763 Plug Co. Name: BLAKE PRODUCTION CO., INC.  
Proposal Rcvd. from: RICK SCHURZ Company: BLAKE PRODUCTION CO., INC. Phone: (785) 567-8686

Proposed Ordered 325 sxs 60/40 pozmix - 500# hulls.  
Plugging Perfs and bridge plugs set a 3184'-3208'; 3236'-3245'; 3162'-3170'; 3144'-3154';  
Method: 3281'-3286'; 3266'-3274'; 3119'-3122'; 3102'-3105'.  
PBSD 3303'.  
Junk in the hole. Bad casing. High fluids.

Plugging Proposal Received By: PAT STAAB WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 06/25/2002 11:30 AM KCC Agent: PAT STAAB

Actual Plugging Report:

Perf Tech shot perfs at 875' and 1475'.  
Express Well Service RIH with tubing to 2680'. Tagged junk in the hole.  
Pulled to 2666' and pumped 25 sxs 60/40 pozmix, followed by 100 sxs with 300# hulls.  
Pulled tubing to 1200' and pumped 150 sxs with 200# hulls to circulate cement.  
Pulled tubing and tied onto casing.  
Pumped 25 sxs with Max. P.S.I. 400#. S.I.P. 200#.  
Tied onto backside and pumped 5 sxs with Max. P.S.I. 500#. S.I.P. 500#.  
Job completed.

RECEIVED  
JUN 28 2002  
KCC WICHITA

Remarks: ORIGINALLY KNOWN AS DONAHEY #1. ALLIED CEMENTING COMPANY-TICKET #6123.

Plugged through: TBG

District: 04

Signed *Pat Staab*  
(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 7-8-02

NO. 2003060007

JUN 26 2002

CITIES SERVICE OIL COMPANY #1 DONAHEY

25-4-20W  
SE SE SW

Contr. \_\_\_\_\_ PHILLIPS County

E 1951 Comm. \_\_\_\_\_ Comp. 10-19-51 IP 11 BOPD & 16 BW  
PHY POT (LANS)

Tops	Depth	Datum
HEEB	3070	-1119
LANS	3114	-1163
B/KC	3324	-1373
T.D.	3340	-1389

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS

Casing  
8" 200 DST 3133-65, 1 HR, 30'  
SLIGHT OIL CUT MUD:  
5" 3340 DST 3180-3221, 1 HR,  
7' MUD: SSO  
DST 3322-39, 1 HR,  
SLIGHT OIL CUT MUD  
PERF 3184-3202,  
3236-45:  
ACID 3000:  
SLINKER POOL PERF 3162-70, 48-56  
3144-54 30-40  
ACID 1000:  
20 BO & 70 BW

+	+	+
+	+	+
+	+	+