

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-039-20409-00-00  
Spot: E2NWSENE Sec/Twnshp/Rge: 23-4S-27W  
990 feet from S Section Line, 700 feet from E Section Line  
Lease/Unit Name: PETRACEK Well Number: 2  
County: DECATUR Total Vertical Depth: 3706 feet

Operator License No.: 4767  
Op Name: RITCHIE EXPLORATION, INC.  
Address: BOX 783188 8100 E 22ND ST. N. #700  
WICHITA, KS 67278

Conductor Pipe: Size feet:  
Surface Casing: Size 8.625 feet: 245 210 SX CMT \$120.45  
Production: Size 4.5 feet: 3692 225 SX CMT  
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 11/07/2001 2:00 PM

Plug Co. License No.: 4767 Plug Co. Name: RITCHIE EXPLORATION, INC.

Proposal Rcvd. from: PETER J. FIORINI Company: RITCHIE EXPLORATION, INC. Phone: (785) 623-1506

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 10% gel - 400# hulls.

Plugging Proposal Received By: DENNIS HAMEL

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 11/07/2001 3:15 PM

KCC Agent: DENNIS HAMEL

Actual Plugging Report:

PBTD at 3630'.  
Plugged 4 1/2" casing with 285 sxs 60/40 pozmix - 10% gel - 400# hulls.  
Max. P.S.I. 300#. S.I.P. 100#.  
Plugged annulus with 30 sxs 60/40 pozmix - 10% gel - 100# hulls.  
Max. P.S.I. 300#. S.I.P. 150#.

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

Dennis L. Hamel  
(TECHNICIAN)

RECEIVED

DEC 04 2001

KCC WICHITA

INVOICED

DATE 12-5-01

INV. NO. 2002061030

Form CP-2/3

NOV 16 2001

A. SCOTT RITCHIE  
 SUITE 950, 125 N. MARKET WICHITA, KS.  
 #2 PETRACEK  
 23-4-27W  
 990' FSL &  
 700' FEL, NE

CONTR MURFIN DRLG. CO. CTY DECATUR

GEOL \_\_\_\_\_ FIELD JENNINGS

E 2567 KB CM 3/24/78 CARD ISSUED 6/15/78 P 25 BOPD + 75% W LANS 3482-3591 OA

|   |   |   |
|---|---|---|
| + | + | + |
| + | + | + |
| + | + | + |

API 15-039-20,409

| LOG  | TOPS | DEPTH | DATUM |
|------|------|-------|-------|
| ANH  |      | 2088  | + 479 |
| TARK |      | 3161  | - 594 |
| HOW  |      | 3250  | - 683 |
| HEEB |      | 3441  | - 874 |
| TOR  |      | 3471  | - 904 |
| LANS |      | 3482  | - 915 |
| LTD  |      | 3649  | -1082 |
| RTD  |      | 3706  | -1139 |
|      |      |       |       |
|      |      |       |       |
|      |      |       |       |
|      |      |       |       |
|      |      |       |       |
|      |      |       |       |
|      |      |       |       |

8-5/8" 245/210sx, 4 1/2" 3692/225sx  
 DST (1) 3148-3230/30-45-60-75, 5' OIL, 97' OCM, N/W, SIP 917-855#, FP 65-76#, 87-98#  
 DST (2) 3451-3490/15-45-45-75 (TOOL PLUGGED) 30' OCM, SIP 842-842#, FP 54-120#, NO FFP  
 DST (3) 3490-3500 (W/SP)/30-45-60-75 60' OIP, 60' SO&HWCM, 830' W W/SC OIL, SIP 819-819#, FP 137-263#, 229-458#  
 DST (4) 3500-3557/30-45-60-75, 1' OIL 60' HO CM, 120' OC TO SOCM, 50' SOCM 10' SO&WCM, SIP 864-864#, FP 57-103#, 103-149#

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS

(OVER)

A. SCOTT RITCHIE #2 PETRACEK 990' FSL & 700' FEL, NE

DST (5) 3558-3572/30-45-60-75, 1' OIL, 29' SO&WCM, 60' SWCM, 180' MCW, SIP 458-458#, FP 34-68#, 80-137#  
 DST (6) 3577-3612/30-45-60-75, 3' OIL, 20' HO CM, 40' OCM, SIP 515-481#, 34-34#, 34-57#  
 DST (7) 3600-3634/30-45-60-75, 30' M, SIP 527-360#, FP 34-34#, 45-45#  
 DST (8) 3628-3656/30-45-60-75, 45' HO CM TO MO, SIP 160-222# FP 22-22#, 34-45#  
 MICT - PBTD 3630', PF 1/3591, 1/3551, 1/3539, SWB 1/4 BF, 50% OIL, AC 2200, SWB AVG 15.55 BFPH, 42% OIL/3 HRS, PF 3590-93 3549-3552, 3538-40, PF 1/3521, 1/3511, 1/3483, BP @ 3534, SWB 2.88 BF, 7% OIL/30", 3.48 BF, 7% OIL/30", 1.16 BF, 7% O/45", AC 2000, SWB AVG 34 BFPH, 10% OIL, PF 3521-24, 3510-13, 3482-84, PULL PLUG & POP