

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-137-20257-00-00
Spot: SENESE Sec/Twnshp/Rge: 12-5S-22W
1650 feet from S Section Line, 330 feet from E Section Line
Lease Name: HOCKMAN Well #: 3
County: NORTON Total Vertical Depth: 3486 feet

Operator License No.: 5552
Op Name: GORE OIL COMPANY
Address: 202 SOUTH ST. FRANCIS PO BOX 2757
WICHITA, KS 67201

PROD Size: 4.5 feet: 3483 125 SX CMT
SURF Size: 8.625 feet: 201 135 SX CMT

113³⁰

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/13/2004 9:30 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: GARY REH Company: GORE OIL COMPANY Phone: (316) 263-3535

Proposed Plugging Method: Ordered out 235 sxs Swift Multi-Density Cement with 500# hulls.
Fluid level 600' from surface.
Ran tubing to plug.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/13/2004 1:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 1800'.
Swift Services pumped 85 sxs SMD with 200# hulls - cement circulated.
PTOH. Squeezed with 60 sxs SMD with 300# hulls.
Max. P.S.I. 900#. S.I.P. 300#.
10-14-2004 - Dug out cellar and orange peeled 8 5/8" to 4 1/2" casing. Swift pumped 35 sxs SMD.
Max. P.S.I. 300#. S.I.P. 50#.

Perfs:

Top	Bot	Thru	Comments
3483	3486		

RECEIVED
OCT 21 2004
KCC WICHITA

Remarks: SWIFT SERVICES, INC.

Plugged through: TBG

District: 04

Signed

Richard Williams

(TECHNICIAN)

INVOICED

DATE 10-21-04

INV. NO. 2005060687

Form CP-2/3

OCT 19 2004

R P NIXON OPERATIONS
 207 W. 12TH #3 HOCKMAN 12-5-22W
 HAYS, KS 67601 SE NE NE
 CONTR JAY-LAN CORP. CTY NORTON loc is SENESE
 GEOL _____ FIELD DENSMORE *per PAT*
 E 2052 KB CM 7/3/82 CARD ISSUED 11/11/82 IP P 10 BOPD, NW
 REAG SD OH 3483-86
 API 15-137-20,257

+	+	+
+	+	+
+	+	+

SMP	Tops	Depth Datum
HEEB	3191-1139
TOR	3218-1166
LANS	3235-1183
BKC	3421-1369
REAG SD	3482-1430
RTD	3486-1434

8 5 8 " 201 135SX; 4 1 2 " 3483
 NO DSTS
 MICT - CO (REAG SD OH), SWB DWN & REC 1.6 BO ' 30", FU
 2300' OIL 14 HRS. SWB DWN & REC 2 BOPD NW, POP

NOTE: ORIGINALLY FIRST REPORTED SE NE SE

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

MADICEN
 0712