

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-137-20300-00-00  
Spot: W2SENE Sec/Twnshp/Rge: 12-5S-22W  
3300 feet from S Section Line, 990 feet from E Section Line  
Lease Name: HOCKMAN Well #: 4  
County: NORTON Total Vertical Depth: 3480 feet

Operator License No.: 5552  
Op Name: GORE OIL COMPANY  
Address: 202 SOUTH ST. FRANCIS PO BOX 2757  
WICHITA, KS 67201

PROD Size: 4.5 feet: 3473 125 SX CMT  
SURF Size: 8.62 feet: 207 135 SX CMT

# 113<sup>10</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/14/2004 8:30 AM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: GARY REH Company: GORE OIL COMPANY Phone: (316) 263-3535

Proposed Plugging Method: Ordered out 235 sxs Swift Multi-Density Cement with 500# hulls.  
Ran tubing to plug. Anhy. 1656'.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 10/15/2004 1:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

MIRU. Ran tubing to 1800'.  
Swift Services pumped 65 sxs SMD with 200# hulls - cement circulated.  
PTOH. Swift pumped 45 sxs SMD with 300# hulls.  
Max. P.S.I. 950#. S.I.P. 600#.  
Rig tore down and moved off.  
Dug out 8 5/8" and orange peeled 8 5/8" to 4 1/2" casing with two inch collar.  
Swift Services pumped 35 sxs SMD.  
Max. P.S.I. 200#. S.I.P. 50#.

Perfs:

Top	Bot	Thru	Comments
3473	3480		
3377	3396		

RECEIVED  
OCT 21 2004  
KCC WICHITA

Remarks: SWIFT SERVICES, INC.

Plugged through: TBG

District: 04


Signed Richard Williams  
(TECHNICIAN)

INVOICED

DATE 10-21-04  
INV. NO. 2005060687

OCT 19 2004

R. P. NIXON OPERATIONS  
 207 W. 12TH #4 HOCKMAN 12-5-22W  
 HAYS, KS 67601 C W/2 SE NE  
 CONTR JAY-LAN CORPORATION CTY NORTON  
 GEOL DAN NIXON FIELD DENSMORE



ELV 2054 KBSPD 9/3/83 CARD ISSUED 11/23/83 IP P 20 BOPD, TR WTR  
 API 15-137-20,300 LKC 3377-3396 OA  
 REAG OH 3473-3480

LOG	Tops	Depth/Datum	
*ANH	1656 + 398		8 5/8 " 207; 4 1/2 " 3473
*B/ANH	1685 + 369		NO CORES OR DSTS
TOP	2927- 873		MICT - CO, (REAG OH), DD 3480 TD, SWB DWN & REC 10 BOPH,
HEEB	3188-1134		NW, NAT, PF (REAG) 1/3475 & (LKC) 1/3396, 1/3377, SET BP AT
TOR	3217-1163		3440', SWB DWN & REC .5 BOPH, NW, NAT, AC 2000 G (28%),
LANS	3232-1178		SWB LD & REC 12 BOPH, NW/2 HRS, DROVE PLUG TO BTM,
BKC	3410-1356		POP, P 116 BOPD, TR WTR, AVER P 20 BOPD, TR WTR, COM-
REAG	3474-1420		MINGLED
RTD	3474-1420		
DDTD	3480-1426		
*SAMPLE TOPS			

COPYRIGHT 1983  
 INDEPENDENT OIL & GAS SERVICE, INC.  
 WICHITA, KANSAS

IMAGED