

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-137-20236-00-00
Spot: NWNESE Sec/Twnshp/Rge: 12-5S-22W
2310 feet from S Section Line, 990 feet from E Section Line
Lease Name: HOCKMAN Well #: 2
County: NORTON Total Vertical Depth: 3494 feet

Operator License No.: 5552
Op Name: GORE OIL COMPANY
Address: 202 SOUTH ST. FRANCIS PO BOX 2757
WICHITA, KS 67201

PROD Size: 4.5 feet: 3491 125 SX CMT
SURF Size: 8.625 feet: 205 135 SX CMT

113⁵⁶

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/14/2004 1:00 PM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: GARY REH Company: GORE OIL COMPANY Phone: (316) 263-3535

Proposed Plugging Method: Ordered out 235 sxs Swift Multi-Density Cement with 500# hulls.
Fluid level 150' from surface.
Ran tubing to plug. Anhy 1656'.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/14/2004 4:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

MIRU. Ran tubing to 1800'.
Swift Services pumped 80 sxs SMD with 200# hulls - cement circulated.
PTOH. Swift squeezed with 65 sxs SMD with 300# hulls.
Max. P.S.I. 700#. S.I.P. 500#.
Tore down rig. Backhoe dug 8 5/8" and orange peeled 8 5/8" to 4 1/2" casing with two inch collar.
Swift pumped 35 sxs SMD.
Max. P.S.I. 200#. S.I.P. 50#.

Perfs:

Top	Bot	Thru	Comments
3360	3396		

RECEIVED
OCT 21 2004
KCC WICHITA

Remarks: SWIFT SERVICES, INC.

Plugged through: TBG

District: 04

1000

Signed Richard Williams
(TECHNICIAN)

INVOICED

DATE 10-21-04
NO. 2005060687

OCT 19 2004

