

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-22869-00-00  
Spot: NW Sec/Twnshp/Rge: 30-11S-19W  
1320 feet from N Section Line, 1320 feet from W Section Line  
Lease Name: SCHONTHALER Well #: 1  
County: ELLIS Total Vertical Depth: 3725 feet

Operator License No.: 32397  
Op Name: CIRCLE S OIL, L.L.C.  
Address: 204 N. FREEMAN  
PLAINVILLE, KS 67663

PROD Size: 4.5 feet: 3725 925 SX CMT  
SURF Size: 8.625 feet: 250 165 SX CMT

#121<sup>06</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/14/2004 9:00 AM  
Plug Co. License No.: 32028 Plug Co. Name: CHITO'S WELL SERVICE, LLC  
Proposal Rcvd. from: DAVID SCHONTHALER Company: CHITO'S WELL SERVICE, LLC Phone: (785) 434-7413

Proposed Plugging Method: Ordered 200 sxs 60/40 pozmix - 10% gel - 600# hulls.  
Well was squeezed. Casing leaks.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 10/14/2004 11:30 AM KCC Agent: PAT STAAB

Actual Plugging Report:

RIH with tubing to 2000'.  
Tied onto tubing and pumped 175 sxs 60/40 pozmix with 500# hulls mixed in to circulate cement to surface.  
Pulled tubing and dug out backside with backhoe.  
Backside was full of cement.  
Tied back onto 4 1/2" casing with a swedge and pumped 25 sxs 60/40 pozmix with 100# hulls mixed in.  
Max. P.S.I. 1000#. S.I.P. 900#.

Perfs:

Top	Bot	Thru	Comments
3681	3687		
3556	3560		
3520	3521		
3440	3442		
3419	3423		
3400	3405		

RECEIVED  
OCT 21 2004  
KCC WICHITA

Remarks: LEASE ORIGINALLY KNOWN AS LUCKY LADY #1. ALLIED CEMENTING COMPANY-TICKET #18911.

Plugged through: TBG

District: 04

Signed

(TECHNICIAN)

INVOICED

DATE

10-21-04

INV. NO.

2005060686

Form CP-2/3

OCT 15 2004

