

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-21186-00-00  
Spot: NWSWNE Sec/Twnshp/Rge: 23-9S-21W  
3630 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: BALTHAZOR KB Well #: 1-A  
County: GRAHAM Total Vertical Depth: 3805 feet

Operator License No.: 5363  
Op Name: BEREXCO, INC.  
Address: PO BOX 20380  
WICHITA, KS 67208

PROD Size: 5.5 feet: 3800 w/200 sxs cmt  
SURF Size: 8.625 feet: 562 w/350 sxs cmt

#123<sup>66</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/13/2004 8:00 AM  
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS  
Proposal Rcvd. from: CURT GABEL Company: BEREXCO, INC. Phone: (785) 628-6101

Proposed Plugging Method: Ordered 365 sxs cement and 500# hulls.  
Perf at 1775' and 1025'.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 10/13/2004 3:00 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

Perfs:

Ran tubing to 3616' - pumped 125 sxs cement with 500# hulls.  
Pulled tubing to 1800' - circulated with 225 sxs cement and 100# hulls.  
Pulled all tubing - squeezed casing with 50 sxs cement.  
Max. P.S.I. 200#. S.I.P. 0#.  
Tied to 8 5/8" x 5 1/2" annulus and squeezed 50 sxs cement.  
Max. P.S.I. 200#. S.I.P. 200#.  
Total of 450 sxs 60/40 pozmix - 10% gel - 600# hulls.  
Dakota 720' - 1014'. Anhy 1743' - 1783'. Salt 2111' - 2169'.

RECEIVED  
OCT 21 2004  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY. BLACKHAWK TANK-WATER.

Plugged through: TBG

District: 04

Signed Roger L. Moses  
(TECHNICIAN)

NOTICED

NOTICED

Form CP-2/3

DATE 10-21-04

DATE \_\_\_\_\_

NO. 2005060684

NO. \_\_\_\_\_

OCT 15 2004

MOBIL OIL CORPORATION

REPLACEMENT CARD

P.O. BOX 5444  
DENVER, CO 80217

#1 'A' BALTHAZOR

23-9-21W


APP NW SW NE

CONTR ABERCROMBIE DRILLING

CTY GRAHAM

GEOL \_\_\_\_\_

FIELD MOREL



ELV 2294 KB SPD 12/26/79 CARD ISSUED 6/12/80

IP P 35 BO & 22 BSWPD

ARB 3972-3795

API 15-065-21,186

LOG	Type	Depth/Datum
SC		1743+ 551
NEVA		2772- 478
TOP		3244- 950
HEEB		3448-1154
DOUG		3458-1164
LANS		3472-1178
ARB		3790-1496
CONG		3747-1453
PBTD		3800-1506
RTD		3805-1511

8 5/8 " 562 / 350 SX, 5 1/2 " 380G / 200 SX  
NO CORES OR DSTS  
MICT - CO, PF (ARB) 12 / 3792-3795, AC 50 GAL (MA) & 80 BBL  
SW FLUSH, SION, SWB DWN, GSO, POP, P 35 BBL NEW OIL &  
22 BSW / 24 HRS

CORRECTION: 10/2/86 - CORRECTED API - WAS 15-067-21,186

COPYRIGHT 1985  
INDEPENDENT OIL & GAS SERVICE, INC.  
WICHITA, KANSAS