

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-039-20685-00-00  
Spot: CN2NWNE Sec/Twnshp/Rge: 23-4S-27W  
330 feet from N Section Line, 1980 feet from E Section Line  
Lease/Unit Name: PETRACEK Well Number: 3  
County: DECATUR Total Vertical Depth: 3678 feet

Operator License No.: 4767  
Op Name: RITCHIE EXPLORATION, INC.  
Address: BOX 783188 8100 E 22ND ST. N. #700  
WICHITA, KS 67278

Conductor Pipe: Size feet:  
Surface Casing: Size 8.625 feet: 267 200 SX CMT \$ 119.54  
Production: Size 4.5 feet: 3675 250 SX CMT  
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 11/07/2001 8:00 AM  
Plug Co. License No.: 4767 Plug Co. Name: RITCHIE EXPLORATION, INC.  
Proposal Rcvd. from: PETER J. FIORNI Company: RITCHIE EXPLORATION, INC. Phone: (785) 623-1506

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 10% gel - 400# hulls.

Plugging Proposal Received By: DENNIS HAMEL Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 11/07/2001 10:40 AM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

PBTD at 3666'.  
Plugged 4 1/2" casing with 200 sxs 60/40 pozmix - 10% gel - 400# hulls.  
Max. P.S.I. 800#. S.I.P. 800#.  
Plugged annulus with 40 sxs 60/40 pozmix - 10% gel - 100# hulls.  
Max. P.S.I. 200#. S.I.P. 100#.

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

Dennis L. Hamel

(TECHNICIAN)

RECEIVED

DEC 04 2001

KCC WICHITA

INVOICED

DATE 12-5-01

INV. NO. 2002061030

Form CP-2/3

NOV 16 2001

REPLACEMENT CARD

A. SCOTT RITCHIE  
 125 N. MARKET, #950  
 WICHITA, KS. 67202

#3 PETRACEK


23-4-27W  
 C N/2 NW NE

CONTR MURFIN DRILLING COMPANY CTY DECATUR

GEOLOGICAL FIELD JENNINGS

ELV 2570 KB SPD 5/24/83 CARD ISSUED 9/15/83 IP OIL WELL

API 15-039-20,685 SHAW(TOR) 3481-3483  
 LKC 3602-3660 OA



LOG	Tops	Depth/Datum
ANH	2103+	467
B/ANH	2135+	435
TARK	3173-	603
HOW	3253-	683
TOP	3279-	709
HEEB	3452-	882
TOR	3480-	910
LANS	3493-	923
LTD	3653-	1083
RTD	3678-	1108

8 5/8 " 267/200 SX, 4 1/2 " 3675/250 SX  
 NO DST'S  
 MICT - CO, PF (LKC) 3658-3660, W / 2 SPF, AC 400 GAL, SWB  
 DWN & REC 55 BF, NO OIL, TSTD 1/2 HR DRY, SWB 1 HR,  
 DRY, PF (J ZN) 3635-3637, W / 2 SPF, SET PLUG AT 3643', AC  
 600 GAL, SWB DWN & REC 56.7 BF, NO OIL, TSTD 1/2 HR DRY,  
 PULL PLUG, PF (H ZN) 3602-3606, W / 2 SPF, SET PLUG AT  
 3620', SWB DWN & TSTD 1/2 HR, DRY, AC 750 GAL, FL 900'  
 DWN, SWB DWN & REC 31 BF, SO / LAST PULL, SWB 1.67 BF  
 (30% OIL) / 1ST HR, 1.67 BF (43% OIL) / 2ND HR, .75 BF (50%  
 OIL) / 3RD HR, SET SD PLUG FROM TD TO 3628', PF (TOR)  
 3481-3483, W / 2 SPF, SET PLUG AT 3500', AC 750 GAL, FL  
 2500', SWB DWN & REC 21.67 BF, LAST PULL (50% OIL), SWB  
 8.35 BF (75% OIL) / 1ST HR, 5.01 BF (78% OIL) / 2ND HR, 3.34  
 BF (81% OIL) / 3RD HR, 1.67 BF (85% OIL) / 4TH HR, 1.67 BF  
 (95% OIL) / 5TH HR, PULLED PLUG, T&R, POP, OIL WELL, 6/28/  
 83, COMMINGLED

CORRECTION: 6/12/86 - CORRECTED ELEV - WAS 2566 KB

COPYRIGHT 1985  
 INDEPENDENT OIL & GAS SERVICE, INC.  
 WICHITA, KANSAS

822-5771