

4- 031787

11-17

149
R

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-137-20,151-00-00
S2 S2 NE /4 SEC. 11, 04 S, 21 W
2970 feet from S section line
1320 feet from E section line

Operator license# 5352 Lease Nuttycomb well # 3

Operator: Baird Oil Company, Inc. County Norton

Address: Box 428 Well total depth 3600 feet
Logan, Kansas 67646 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 252 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: B.J. Services License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: P.M. Day: 17 Month: November Year: 92

Plugging proposal received from: Jim Baird

Company: Baird Oil Company, Inc. Phone: _____

Were: Order 350 sx. 65/35 pozmix - 10% gel. - 500# hulls.
Hole open to perf.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour: 12:30P.M., Day: 17, Month: November, Year: 92

Actual plugging report: 8 5/8" set @ 252' w/200 sx. cwc. 4 1/2" set @
3597' w/235 sx. P.B.T.D. 3579'. Perf. 3406' - 3497'. Critical zone
shots @ 1115' and 1790'. Squeezed 4 1/2" casing w/250 sx. cement blend
w/400# hulls mixed into Max. P.S.I. 500#. Close in P.S.I. 300#.
Squeezed 8 5/8" w/100 sx. cement blend w/100# hulls mixed in to Max.
P.S.I. 300#. Close in P.S.I. 200#. Plug complete.

RECEIVED
STATE CORPORATION COMMISSION

Remarks: _____
Condition of casing(in hole): GOOD BAD Any plug: YES NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING _____, CASING . Elevation: _____ GL

DEC 7 1992

I did / did not observe the plugging. Carl Goodrow

INVOICED
DATE 12-9-92
INV. NO. 37026

(agent)
Form CP-2/3