

6 040755

MAY 14 1987 15-147-20075-0001

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- E-15,367  
1969

SW SW NE, SEC. 19, T 4 S, R 19

\_\_\_\_\_ feet from S section line

\_\_\_\_\_ feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5242

Lease Name Merklein Well # 1

Operator: Petroleum Mgmt. Inc.

County Phillips 110.50

Name & Address 400 N. Woodlawn

Well Total Depth 3400 feet

Suite 201

Conductor Pipe: Size \_\_\_\_\_ feet

Wichita, Ks. 67208

Surface Casing: Size 8 5/8" feet 210 w/145

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well  SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Allied Cementing License Number \_\_\_\_\_

Address Russell, Ks.

Company to plug at: Hour: 7:00 AM Day: 14 Month: May Year: 19 87

Plugging proposal received from Wayne Fuzzell

(company name) P.M.T. (phone) \_\_\_\_\_

were: 4 1/2" csg. set at 3394' w/250 sks. cement. Perf at 3187 - 91, 3220 -24, 3256 -60,

3274 -76; Hole in casing at 1039' (BASE DAKOTA @ 960')

Ordered 200 sks 65/35 Poz, 10% Gel, 1/4# Flocele and 8 sks. Hulls.

Plugging Proposal Received by Dennis Hamel  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 6:30 PM Day: 14 Month: May Year: 19 87

ACTUAL PLUGGING REPORT Pumped in 4 1/2" csg w/25 sks cement 100 sks cement w/4 sks. Hulls

(slight blow on annulus)

Max P.S.I. 800# Shut in 500#

Pumped in 8 5/8" S.P. 75 sks cmt. w/4 sks. Hulls.

Max. P.S.I. 600# Shut in 300#.

RECEIVED  
STATE CORPORATION COMMISSION

Remarks: (if additional description is necessary, use BACK of this form.)

INVOICED

Observe this plugging.

JUN 5 1987

CONSERVATION DIVISION  
Wichita, Kansas

DATE 6-5-87

Signed Dennis L. Hamel  
(TECHNICIAN)

INV. NO. 17176

Dennis L. Hamel