

4-042024

15-147-20038-00-00

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

10-15

API Number: 15- - 5-20-68

SW SE NW /4 SEC. 19, 04 S, 19 W  
2970 feet from S section line  
3630 feet from E Section line

Operator license# 3077

Lease: Slinker Well # 1

Operator: Johnson Oil Company

County: Phillips

Address: P.O. Box 35 - R.R. 3  
Phillipsburg, Ks 67661

Well total depth 3447 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface Pipe: 8 5/8 Inch 206 Feet  
W/cwc

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 8:00 A.M. Day: 15 Month: October Year: 1999

Plugging proposal received from: Kevin Johnson

Company: Johnson Oil Company Phone: -

Were: Ordered 200 sxs 60/40 pozmix - 10% gel with 1/4# F.C. plus 200# hulls.  
4 1/2" casing set at 3447' w/100 sxs cement. Perfs at 3266' - 3341'.  
Holes in casing - tubing cemented in at 3046' with 400 sxs cement with TOC of cement  
in casing at 460'. Cement in tubing at bottom.

INVOICED

DATE 10-26-99  
60743

Plugging Proposal Received by: Dennis Hamel

Plugging operations attended by agent? All [ X ], Part [ ], None [ ]

Completed: Hour: 10:00 A.M., Day: 15, Month: October, Year: 1999

Actual plugging report: Swab tubing dry. R.U. Cementers. Squeezed 55 sxs cement down 2 3/8" tubing with 50# hulls. Max. P.S.I. 500#. Squeezed down 2 3/8" x 4 1/2" with 40 sxs cement with 50# hulls. Max. P.S.I. 400#. Squeezed 8 5/8" S.P. with 50 sxs cement with 100# hulls. Max. P.S.I. 300#.

Remarks:

Condition of casing(in hole): GOOD BAD X Anhy.plug: YES X NO

Bottom plug(in place): YES X, CALC, NO Dakota plug: YES X, NO

Plugged through TUBING CASING X Elevation: G.L.

I did [ X ] / did not [ ] observe the plugging.

REC Dennis J. Hamel  
KANSAS CORPORATION COMMISSION (agent)

Form CP-2/3

OCT 20 1999  
10-20-99

(Handwritten circle with '2')