

6-13

1100

6 010712

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 137-20,150 -00-01
NE, SEC. 11, T 4, S, R 21 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5352

4290 feet from S section line
1420 feet from E section line

Operator: Baird Oil Co.
Name & Address: Box 428
Logan, Ks. 67646

Lease Name Nuttycomb Well # 2
County Norton 117.68

Well Total Depth 3621 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 248 w/200 sks

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Baird Oil Co. License Number _____
Address Logan, Ks.

Company to plug at: Hour: 9:00 AM Day: 13 Month: June Year: 19 90

Plugging proposal received from James Baird

(company name) Baird Oil Co. (phone) _____

were: Order 100 sks common cement w/2 sks f.c. and 250 sks 65/35poz gel 690

P.B. T.D. 1800. 4 1/2 casing at 3620. Perf 1490 - 1520.

Anhydrite 1810-40. Sq w/350 sks cement at 1829.

Plugging Proposal Received by _____ D.F.B.
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:15AM Day: 13 Month: June Year: 19 90

ACTUAL PLUGGING REPORT Ran tubing to 1800 tagged P.B.T.D.

pulled 1 joint tubing. Pumped down tubing 100 sks common cement. Pulled 700' tubing.

Pumped down 75 sks cement. Pulled tubing. Sq, 15 sks cement. Locked up w/750#. Pumped down

8 5/8" 25 sks cement w/200#. Squeezed

STATE CORPORATION COMMISSION
7-12-90
JUL 12 1990

Remarks: Allied. CONSERVATION DIVISION
Wichita, Kansas

INVOICED

If additional description is necessary, use BACK of this form.)

DATE 7-17-90

INV. NO. 28585

Gib S.

Signed Dale F. Balthazor
(TECHNICIAN)