

15-137-20149-00-00

6 030881

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 11-1-79
350' EC
N/2 N/2 SE, SEC. 11, T 4 S, R 21 (W/E)

2310 feet from S section line
970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5352

Lease Name Nichol Well # 1

Operator: Baird Oil Co. Inc.
Name & Address: Box 428
Logan, Ks. 67646

County Norton 115.70

Well Total Depth 3560 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 249'

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing License Number 6050

Address Chase, Ks.

Company to plug at: Hour: AM Day: _____ Month: _____ Year: 19 87

Plugging proposal received from Millard Kelso

(company name) Kelso Casing (phone) _____

were: 8 5/8 set at 249' cwc 4 1/2" set at 3618' with 235 sx perf 3424-3564 order com. sand
and cement- shoot and strip pipe order 150 sx ATL 65/35 pox 10% gel 2% dicel
5 sk hulls. Allied Cement Co.

Plugging Proposal Received by Dale Balthazor & Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 11:AM Day: 18 Month: 5 Year: 19 87

ACTUAL PLUGGING REPORT Dump sand to 3375' spot 4 sx com cmt. on sand with bailer.

3 shots at 1200-100-442 recovered 442' of 4 1/2" csg. Mix and pump down 8 5/8 csg.
5 sx hulls with 150 sx cmt blend max PSI 600 # close in 150 # plug complete.

RECEIVED
STATE CORPORATION COMMISSION

JUL 16 1987 7-16-87

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Plug checked by Dale B. OK
(If additional description is necessary, use BACK of this form.)

INVOICED

(did / did not) observe this plugging.

DATE 7-16-87

Signed Carl Goodrow
(TECHNICIAN)
Carl Goodrow

INV. NO. 17501