

4- 031788

11-17

150 R

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-137-20,145 -00-00

N2 S2 NE /4 SEC. 11, 04 S, 21 W
2530 feet from S section line
1320 feet from E section line

Operator license# 5352

Lease Nuttycomb well # 1

Operator: Baird Oil Company, Inc.

County Norton

Address: Box 428
Logan, Kansas 67646

Well total depth 3610 feet ^{117.33}
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 246 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: B.J. Services License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: A.M. Day: 17 Month: November Year: 92

Plugging proposal received from: Jim Baird

Company: Baird Oil Company, Inc. Phone:

Were: Order 350 sx. 65/35 pozmix - 10% gel. - 500# hulls.
Hole open to perf.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 10:20A.M., Day: 17, Month: November, Year: 92

Actual plugging report: 8 5/8" set @ 246' w/200 sx. cwc. 4 1/2" set @ 3606' w/235 sx. P.B.T.D. 3588'. Perf. 3385' - 3542'. Critical zone shots @ 1125' and 1800'. Squeezed 4 1/2" casing w/245 sx. cement blend w/400# hulls mixed into Max. P.S.I. 400#. Close in P.S.I. 200#. Squeezed 8 5/8" w/105 sx. cement blend w/100# hulls mixed in to Max. P.S.I. 500#. Close in P.S.I. 400#. Plug complete.

RECEIVED
STATE CORPORATION COMMISSION

Remarks:

Condition of casing(in hole): GOOD X BAD Any plug: YES X NO
Bottom plug(in place): YES , CALC X, NO Dakota plug: YES X, NO
Plugged through TUBING , CASING X. Elevation: GL

I did X / did not] observe the plugging.

Carl Goodrow

DATE 12-9-92

INV. NO. 37027

(agent)

Form CP-2/3