

9-15

TO:
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING
 130 SOUTH MARKET, SUITE 2078
 WICHITA, KANSAS 67202

API Number: 15-137-20,411-0000

E2 NE SE /4 SEC. 04, 04 S, 21 W
 1980 feet from S section line
 330 feet from E section line

Operator license# 32016

Lease: Van Loenen Well # 1

Operator: Pioneer Resources

County: Norton

Address: R.R. 2 - Box 47A
 Phillipsburg, Kansas 67661

Well total depth 3690 119.93 feet
 Conductor Pipe: 0 inch @ 0 feet
 Surface pipe 8 5/8 Inch @ 263 feet

Aband. oil well____, Gas well____, Input well____, SWD____, D & A X

Plugging contractor: Discovery Drilling License# 31548

Address: Hays, Kansas 67601

Company to plug at: Hour: 5:30 A.M. Day: 15 Month: September Year: 1999

Plugging proposal received from: Tom Alm

Company: Discovery Drilling Phone: -

Were: Order 200 sxs 60/40 posmix - 6% gel with 1/4# flocele per sack.
 Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All [] , Part [] , None [X]

Completed: Hour 8:30 A.M. , Day: 15, Month: September , Year: 1999

Actual plugging report:
 1st. Plug at 1940' w/25 sxs cement. Anhydrite 1910' - 1940'.
 2nd. Plug at 1150' w/100 sxs cement. Dakota 849' - 1149'.
 3rd. Plug at 315' w/40 sxs cement. Surface pipe to 263'.
 4th. Plug at 40' w/10 sxs cement.
 15 sxs in rathole.
 10 sxs in mousehole.

Remarks: Allied Cementing.

Condition of casing in hole): GOOD BAD _____ Anhy. plug: YES NO _____
 Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO _____
 Plugged through TUBING _____, CASING _____. Elevation: _____ GL

I did[] / did not[X] observe the plugging.


 (agent)
 Form CP-2/3

INVOICED
 DATE 9-30-99
 REC'D. 2000610625

RECEIVED
 STATE CORPORATION COMMISSION

SEP 24 1999

CONSERVATION DIVISION
 Wichita, Kansas

