

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-147-20124-00-00
Spot: CSEnwSE Sec/Twnshp/Rge: 16-4S-19W
1650 feet from S Section Line, 1650 feet from E Section Line
Lease/Unit Name: BRUNING Well Number: 1
County: PHILLIPS Total Vertical Depth: 3578 feet

Operator License No.: 32819
Op Name: BAIRD OIL COMPANY LLC
Address: 113 W. MAIN - PO BOX 428
LOGAN, KS 67646

Conductor Pipe: Size _____ feet:
Surface Casing: Size 8.625 feet: 220 155 SX CMT
Production: Size 4.5 feet: 3574 150 SX CMT
Liner: Size _____ feet:

8/16.29

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/04/2001 8:00 AM

Plug Co. License No.: 32819 Plug Co. Name: BAIRD OIL COMPANY LLC

Proposal Revd. from: JIM R. BAIRD Company: BAIRD OIL COMPANY LLC Phone: (785) 689-7456

Proposed Plugging Method: Order 9 yards Redi-Mix - 5 sxs common cement - 3000# sand with 42 gallons water per yards.

Plugging Proposal Received By: CARL GOODROW Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 09/04/2001 9:40 AM KCC Agent: CARL GOODROW

Actual Plugging Report:

8 5/8" set at 220' w/155 sxs cwc. 4 1/2" set at 3574' w/150 sxs.
Prod.Perfs 3245' - 3252'. PBTD 3530'.
Fluid Level low.
Cut off casing - filled 8 5/8" annulus and 4 1/2" with 9 yards Redi-Mix.
Plug complete.

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Carl Goodrow
(TECHNICIAN)

RECEIVED
09-18-2001
SEP 18 2001


INVOICED
DATE 9-18-01
INV. NO. 2002060486

Form CP-2/3

SEP 07 2001

KCC WICHITA

R. W. RINE DRILLING CO. #1 BRUNING 16-4-19W
 WICHITA, KANSAS SE NW SE
 CONTR B & B DRILLING CO. CTY PHILLIPS
 GEOL PAUL HARPER FIELD WOLF CREEK REV.
 E. 2021 KB CM6/22/71 CARD ISSUED 9/2/71 IP P 27 BOPD + 60% WTR
 KC 3248-52 GR 39



API 15-147-20,124

LOG	TOPS	DEPTH	DATUM
HEEB		3169	-1148
TOR		3195	-1174
LKC		3211	-1190
BKC		3431	-1410
B MRM		3515	-1494
RTD		3538	-1517

8 5/8" 222/155SX; 4 1/2" 3474/150SX
 DST(1) 3192-3250/30-45-90-45, 210' GIP,
 80' CFO, 10' MO, 60' VHOCM, 60' HOCM, BHP
 1213-1181#, FP 52-63# & 82-116#
 DST(2) 3254-70/15-30-60-30, 260' MW(NS)
 BHP 1171-1081#, FP 6-27# & 52-137#
 DST(3) 3276-3305/15-30-30-30, 3' M W/SP
 FO, BHP 643-355#, FP 16-16# & 21-21#
 MICT, SWB TO 3340 PF 8/3245-52 SWB 14
 GM & BRACKISH WTR W/SFO/30" SWB 22GMW
 W/GSO 2ND 30" SWB 28GF SWB 38GF (WTR MDY)
 A500MCA (LD 65B) SWB ED SWB 15.75BF 65%W
 SD/14HRS FU 2448' FL (1040' OIL + 1408' W)
 SWB 6.3BFP/5HRS 40% OIL SD/14HRS FU
 2273' FL 40% OIL

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS