

6 010603

3-24-88 15-147-20151-00136 R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- April 1972

NW NE NW, SEC. 15, T 4 S, R 19 (W/E)
3630 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4807

Lease Name Morgan Well # 1

Operator: G. K. M. Inc.

County 112.03 Phillips

Name & Address Box 520

Well Total Depth 3447 feet

Great Bend, Ks.

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 207 cwc

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Company License Number 4807

Address Same

Company to plug at: Hour: PM Day: 24 Month: Mar Year: 19 88

Plugging proposal received from Jerry Rice

(company name) Same (phone)

were: Order 50 sks Common Cement 300 sks 65/35 Poz 10% Gel 2% Lite
450# Hulls. 4 1/2" at 3447' w/175 sks cement. 2" tubing 3338'. Shot off at
2805'. Wireline tagged at 2657'. 4 1/2" squeezed at 900' - 1120'. Holes in
pipe from 1595' - 1770'. Elev. 2062'. Top Dakota 687'.

Plugging Proposal Received by D. F. B. (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: Day: 24 Month: Mar Year: 19 88

ACTUAL PLUGGING REPORT Pumped down 4 1/2" 50 sks Common Cement. Then, 150 sks
Lite w/300# Hulls. Pumped down 8 5/8" 40 sks Cement w/150# Hulls.

Casing max pressure 1100#. casing closed w/600# pressure 8 5/8 max 850# Closed
400#.

RECEIVED
STATE CORPORATION COMMISSION
APR 22 1988
04-22-1988
CONSERVATION DIVISION
Wichita, Kansas

Remarks: B. J. Titan Cement Co.
(If additional description is necessary, use BACK of this form.)

INVOICED
I hereby certify that I have served this plugging.

Signed Dale F. Balthazor (TECHNICIAN)
Dale F. Balthazor

DATE 4-26-88
INV. NO. 20449