

4-032066

6-14

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-147-20,132-00-00

NW SE NW /4 SEC. 15, 04 S, 19 W
3590 feet from S section line
3590 feet from E section line

Operator license# 5242

Lease: Henry EHM Well # 1

Operator: Petroleum Management, Inc.

County: Phillips

Address: 14201 E. Central
Wichita, Kansas 67230

Well total depth 3520 114.40 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8% Inch @ 226 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cement Company License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: A.M. Day: 14 Month: June Year: 1995

Plugging proposal received from: Don Keener

Company: Petroleum Management, Inc. Phone:

Were: Order 250 sxs. 60/40 posmix - 10% gel - 500# hulls.
Perf. 1620' and 1000'.

RECEIVED
STATE CORPORATION COMMISSION
JUL 03 1995
07-03-1995
CONSERVATION DIVISION
WICHITA, KANSAS

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 10:30 A.M., Day: 14, Month: June, Year: 1995

Actual plugging report: 8 5/8" set at 226' w/160 sxs cwc. 4 1/2" set at 3519' w/250 sxs.
Squeezed 1590' and 1062' with 350 sxs. Prod. Perf. 3304' - 3421'. Critical control shots at
1620' and 1000'. Squeezed 4 1/2" with 190 sxs cement blend with 500# hulls to Max. P.S.I.
500#. Close in P.S.I. 200#. Squeezed 8 5/8" with 50 sxs cement blend to Max. P.S.I. 150#.
Close in P.S.I. 150#. Plug complete.

Remarks:
Condition of casing(in hole): GOOD BAD Anhy.plug: YES 1601 NO
Bottom plug(in place): YES, CALC KCC Dakota plug: YES X, NO
Plugged through TURING, CASING Elevation: 2093 GL

I did [X] / did not [] observe the plugging.
DATE 7-7-95
INV. NO. 43047

JUN 30 1995
HAYS, KS

Carl Goodrow
(agent)