

4-032171

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-137-20,397-0000

SW SW SW /4 SEC. 13, 04, 22 W
330 feet from S section line
330 feet from W section line

8-2

Operator license# 5050 Lease: Bales Well # 1

Operator: Hummon Corporation County: Norton 118.10

Address: 200 W. Douglas - #1020 Well total depth 3634 feet
Wichita, Kansas 67202 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 250 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cement Company License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: A.M. Day: 2 Month: August Year: 1996

Plugging proposal received from: Tom

Company: Hummon Corporation Phone: -

Were: Order 320 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 10:15 A.M., Day: 2, Month: August, Year: 1996

RECEIVED
KANSAS CORP CO. INC.
AUG 12 12 54

S-12-96

Actual plugging report: 8 5/8" set at 250' cwc with 150 sxs. 5 1/2" set at 3628' with 100 sxs. Port collar at 1812' cwc 350 sxs. Squeezed 5 1/2" with 280 sxs cement blend with 500# hulls mixed in to Max. P.S.I. 1300#. Held 800#. Cement in 8 5/8" annulus at surface. Plugged two water wells with 10 sxs each for total of 20 sxs. Plug complete.

Remarks: Condition of casing(in hole): GOOD BAD Anhy.plug: YES X NO
Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO
Plugged through TUBING, CASING. Elevation: GL

I did [X] / did not [] observe the plugging.

Carl Goodrow (agent)

OKD

INVOICED
AUG 16 1996

Form CP-2/3

DATE
INV. NO. 46266