

4-031871

10-13

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-137-20,389 -00-00

S2 SW NW /4 SEC. 24, 04 S, 22 W
2970 feet from S section line
4650 feet from E section line

Operator license# 5030

Lease Greving well # 1-24

Operator: Vess Oil Corporation

County Norton

Address: 8100 E. 22nd. Street
North Building #300
Wichita, Kansas 67226

Well total depth 3700 feet ^{120.25}
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 213 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Murfin Drilling License# 30606

Address: Hill City, Kansas

Company to plug at: Hour: P.M. Day: 13 Month: October Year: 93

Plugging proposal received from: Kevin

Company: Murfin Drilling Phone: _____

Were: Order 225 sxs. 65/35 pozmix - 10% gel - 500# hulls.
Pull casing.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour: 12:30P.M., Day: 13, Month: October, Year: 93

Actual plugging report: 8 5/8" set @ 213' w/140 sxs. cwc. 4 1/2" set @
3699' w/175 sxs. Prod. PF. 3608' - 3621'. PBSD 3668' to 2708'. Shot
@ 1790' tight. Recovered 1030' from free point. Mixed and pumped
100 sxs. cement blend w/500# hulls mixed in w/600# P.S.I. Laid down
casing topped off w/35 sxs. cement blend with cement in cellar.
Plug complete.

Remarks:

Condition of casing(in hole): GOOD BAD Anhy. plug: YES NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING , CASING . Elevation: _____ GL

I did] observe the plugging.

Carl Goodrow
HO. (agent)

RECEIVED
STATE CORPORATION COMMISSION
NOV 05 1993
11-5-93
CONSERVATION DIVISION
Wichita, Kansas

INVOICED
DATE 11-8-93
INV. NO. 39171