

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-137-20,264-00-00  
NW, Sec. 28, T 4 S, R 22 W/E

990 feet from N/S section line  
990 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5005

Lease Name Sperry Well # 1

Operator: Sunburst Exploration Co.  
Name & Address 708 One Main Place  
Wichita, Ks. 67202

County Norton

Well Total Depth 3815 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8" feet 345

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Abercrombie Drilling, Inc. License Number 182

Address 801 Union Center, Wichita, Ks 67202

Company to plug at: Hour: 10:00 PM Day: 21 Month: 10 Year: 1982

VERBAL PLUGGING ORDERS GIVEN TO Bill Craig

(company name) Abercrombie Drilling, Inc. (phone) 316-262-1841

were: Order out 180 sacks 50 posmix - 6% Gel - 3% Col. Cl. + 8 5/8" plug. Spot w/drill stem w/ heavy mud between all plugs. 1st plug 1950' w/ 20 sacks, 2nd 1500' w/ 100 sacks, 3rd plug C 400' w/ 40 sacks, 4th plug - solid bridge of hulls + plug C 40' w/ 10 sacks.

Circulate 10 sacks in rat hole

Signed G. E. Schel  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 11:30 PM Day: 21 Month: 10 Year: 1982

ACTUAL PLUGGING REPORT 8 5/8" - 345' SP. cas. w/ 280 sacks common - 2% Gel - 3% Col. Cl.

Ordered out 180 sacks 50 posmix - 6% Gel - 3% Col. Cl. + 8 5/8" plug. Spot w/drill stem w/ heavy mud between all plugs. 1st plug C 1950' w/ 20 sacks, 2nd plug C 1500' w/ 100 sacks, 3rd plug C 400' w/ 40 sacks, 4th plug - solid bridge C 40' w/ 10 sacks.

Circulated 10 sacks in rat hole.

Remarks: \_\_\_\_\_

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 1 1982  
CONSERVATION DIVISION  
Wichita, Kansas  
11-1-82

I hereby certify that the above plugging instructions were given as shown in stated and that I (did / did not) observe this plugging.

INVOICED

DATE 11-1-82

INV. NO. 1650-W

Signed G. E. Schel  
(TECHNICIAN)

FORM CP-2/3  
Rev. 9-82