

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-147-20132-00-00

LEASE NAME HENRY EHM

WELL NUMBER #1

TYPE OR PRINT
NOTICE: Fill out **completely**
and return to Cons. Div.
office within 30 days.

3590 Ft. from S Section Line

3590 Ft. from E Section Line

LEASE OPERATOR Petroleum Management, Inc.

SEC. 15 TWP. 4 RGE. 19 (E) or (W)

ADDRESS 14201 E. Central, Wichita, KS 67230

COUNTY Phillips

PHONE#(316) 733-5600 OPERATORS LICENSE NO. 5242

Date Well Completed 8/19/71

Character of Well Oil

Plugging Commenced 6/14/95

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 6/14/95

The plugging proposal was approved on 5/18/95 (date)

by David P. Williams (KCC District Agent's Name).

Is ACO-1 filed? No If not, Is well log attached? Yes

Producing Formation L/KC Depth to Top 3304 Bottom 3308 T.D. 3520

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	226	0
				4 1/2	3519	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Mixed 50 sxs cement with 1 sx hulls down 8 5/8" at 150 psi, shutin @ 150#. Mixed 190 sxs 60/80 Pozmix, 10% Gel with 4 sxs hulls down 4 1/2" at 500 psi, shutin at 200#. Perf at 1000-1001' and 1620-1624' before poumping down casing.

(if additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Company, Inc. License No.

Address P. O. Box 31, Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Petroleum Management, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Gary L. Reed


(Employee of Operator) (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Gary L. Reed

(Address) 14201 E. Central, Wichita, KS

DEPENDED AND SWORN TO before me this 11th day of July, 19 95



Kathleen L. Carter
Notary Public

My Commission Expires:

RECEIVED
KANSAS CORPORATION COMMISSION
JUL 12 1995
07-12-1995
CONSERVATION DIVISION
WICHITA, KS

DRILLERS LOG

15-147-20132-00-00

No. 1 Ehm

CASING RECORD:

8 5/8" @ 226
w/160 sx cement

4 1/2" @ 3519'
w/250 sx cement

TOTAL DEPTH: 3520'

COMPANY:

Petroleum Management, Inc.

CONTRACTOR:

Red Tiger Drilling Co.

COMMENCED:

August 13, 1971

COMPLETED:

August 19, 1971

DESCRIPTION:

NW SE NW
15-4S-19W
Phillips County,
Kansas

ELEVATION:

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Clay sand	0	40	
Sand & shale	40	755	
Shale, sand & red bed	755	1601	
Anhydrite	1601	1631	
Shale	1631	1755	
Shale & shells	1755	2307	
Shale & Lime	2307	3045	
Lime	3045	3520	

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RECEIVED
KANSAS CORPORATION COMMISSION


RED TIGER DRILLING COMPANY

JUL 12 1995

CONSERVATION DIVISION
WICHITA, KS

Jim Farrice
Jim Farrice

Subscribed and sworn to before me this 24th day of August, 1971.



Virginia K. Albert
Notary Public

My Commission Expires: July 23, 1974