

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

#4 15-147-20151-00-00

API NUMBER COMP-4-72

LEASE NAME MOTYAN

WELL NUMBER 1  
 \_\_\_\_\_ Ft. from S Section Line  
 \_\_\_\_\_ Ft. from E Section Line

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR GKM INC.

ADDRESS P.O. Box 520 Great Bend KS. 67530

PHONE# (316) 792-3571 OPERATORS LICENSE NO. 4807

Character of Well OIL

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

SEC. 15 TWP. 4-S RGE. 19 (E) or (W)

COUNTY Phillips

Date Well Completed 4-72

Plugging Commenced 3-24-88

Plugging Completed 3-24-88

The plugging proposal was approved on 3-18-88 (date)

by Dale Baithazor (KCC District Agent's Name)

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing Formation K.C. + LANSING Depth to Top 3212 Bottom 3384 T.D. 3457

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
LANSING K.C.	OIL + water	3212	3384	4 1/2	3450	NONE
	FRESH water	0	207'	8 5/8	207'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each. PUMPED DOWN 4 1/2 CS9 50 SX OF COMMON CEMENT 150 SX OF LITE CEMENT 300# OF HULLS MAX P.S.T 1100 # S.I. Press 600 # PUMPED DOWN 8 5/8 40 SX OF LITE CEMENT 150 SX OF HULLS ST. PLESS. 850 #

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor B J TITAN License No. 30 1988

Address 1910 18th St Great Bend KS. 67530

STATE OF KANSAS COUNTY OF BRANTON, ss.

Jerry L. Rice (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed therewith and the same are true and correct, so help me God.

(Signature) Jerry L. Rice

(Address) P.O. Box 520 Great Bend KS.

SUBSCRIBED AND SWORN TO before me this 29 day of March, 19 88

Ramona L. Dunlap  
 Notary Public

My Commission Expires: 1-23-92

