

RECEIVED
 KANSAS CORP COMM.
 NOTICE: Fill out completely and return to Cons. Div. office within 30 days.

WELL NUMBER 1
2310 Ft. from S/N Line of Section (circle one)

3630 Ft. from E/W Line of Section (circle one)
 SPOT LOCATION W/2 N/W1/4 SE NW 1/4

SEC. 19 TWP. 4S S. RGE. 19W (E) or (W)
 COUNTY Phillips

Date Well Completed 5-20-1968

Date Plugging Commenced 10-15-1999

Date Plugging Completed 10-15-1999

LEASE OPERATOR Johnson Oil
 ADDRESS Box 35 RR 3

CITY, STATE, ZIP Phillipsburg Kansas

PHONE# 785-543-6171 OPERATORS LICENSE NO. 3077

Character of Well OIL WELL
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on Emergency plugging (date)
 by Dennis Hammel District #4 (KCC District Agent's Name)

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation(s) Lansing Kansas city Depth to Top 3266 Bottom 3341 T.D. 3421

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
Lansing production	OIL	3266	3270	4 1/2	3447	none
IK/c production	oil	3337	3341	4 1/2	3447	none
surface casing				8 5/8	206"	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Pumped down 2 3/8 tubing with 55 sacks with 50 lbs of hals press to 500 lbs.
 Pumped down 8 5/8 with 50 sacks and 100 lbs of hals pressured to 500lbs.
 Pumped between 2" and 4 1/2 40 sacks and 50 lbs of hals pressured to 400 lbs.
 cement stood at surface.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor ALLIED CEMENTING

License No. N/A

Address Russell Kansas

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: JOHNSON OIL

STATE OF KANSAS COUNTY OF Phillips, ss.
KEVIN JOHNSON

(Employee of Operator or (Operator) of above-described well, being first

duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]
 (Address) Box 35 RR 3 PHILLIPSBURG KS 67661

SUBSCRIBED AND SWORN TO before me this 25th day of OCTOBER, 1999

My Commission Expires: 11 April 2001
 Notary Public

