

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas. 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-147-20043-00-01
API NUMBER N/A

LEASE NAME Slinker

WELL NUMBER 2

3630 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 19 TWP. 4 RGE. 19 ~~XX~~ or (W)

COUNTY Phillips

Date Well Completed 8/68 *KCC ops*

Plugging Commenced 5/14/87

Plugging Completed 5/14/87

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Petroleum Management, Inc.

ADDRESS 400 N. Woodlawn, Suite 201, Wichita, KS 67208

PHONE# (316) 686-7287 OPERATORS LICENSE NO. 5242

Character of Well Water Supply Well *EOR KCC ops*

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays

Is ACO-1 filed? N/A If not, is well log attached? Already submitted with plugging application.

Producing Formation Lansing/K.C. Depth to Top 3180' Bottom 3332' T.D. 3400'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Lansing/K.C.	Oil	0	3397'	4 1/2"	3347'	0'
Cedar Hills	Water	0	218'	8 5/8"	218'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Pumped 125 sx 35/65 Pozmix w/4 sx hulls down 4 1/2" casing and 75 sx 35/65 Pozmix down 8 5/8" casing w/4 sx hulls.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Petroleum Management, Inc. License No. 731

Address P. O. Box H, Plainville, KS 67663

STATE OF Kansas COUNTY OF Sedgwick, ss.

R. D. Reber, Jr. (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) R. D. Reber, Jr.

(Address) 400 N. Woodlawn, Wichita, KS 67208

SUBSCRIBED AND SWORN TO before me this 1st day of June, 1987

RECEIVED
STATE CORPORATION COMMISSION
Brown
Notary Public

My Commission Expires



JUN 3 1987
06-03-1987
Form CP-4
Wichita, Kansas
Revised 08-84

AUG 08 1968

15-147-20043-00-0

DRILLERS LOG

No. 2 Slinker

CASING RECORD:	COMPANY:	Petroleum Management, Inc.	DESCRIPTION:
8 5/8" @ 218'	CONTRACTOR:	Red Tiger Drilling Company	NE SE NW
w/160 sx cement	COMMENCED:	July 24, 1968	19-4S-19W
4 1/2" @ 3397'	COMPLETED:	July 31, 1968	Phillips Co.,
w/250 sx cement			Kansas
TOTAL DEPTH: 3400'			ELEVATION:

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Clay and Sand	0	40	
Clay, sand and shale	40	218	
Shale	218	1040	
Sand	1040	1250	
Shale	2150	1525	
Anhydrite	1525	1558	
Shale and shells	1558	1760	
Shale, shells, Lime streaks	1760	1995	
Shale w/Lime	1995	2995	
Lime	2995	3400	

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Norman E. Klein
Norman E. Klein

Subscribed and sworn to before me this 7th day of August, 1968.