

RECEIVED  
 STATE CORPORATION COMMISSION  
 SEP 20 1988

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE NAME Schneider  
 WELL NUMBER B-1  
330' Ft. from S Section Line  
1650' Ft. from E Section Line  
 SEC. 19 TWP. 4S RGE. 19 ~~06E~~ or (W)

LEASE OPERATOR CONSERVATION DIVISION  
Petroleum Management, Inc.  
 ADDRESS 400 N. Woodlawn, Suite 201, Wichita, KS 67208

COUNTY Phillips  
 Date Well Completed April 1972  
 Plugging Commenced 9/1/88  
 Plugging Completed 9/1/88

PHONE#(316) 686-7287 OPERATORS LICENSE NO. 5242  
 Character of Well Oil FDR KCC ap  
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 5/26/88 (date)  
 by Hays (KCC District Agent's Name).

Is ACO-1 filed? no If not, is well log attached? no-filed w/application  
 Producing Formation Kansas City Depth to Top 3117' Bottom 3282' T.D. 3380'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
LKC	oil			8-5/8"	208'	0
				4-1/2"	3378'	735'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
Plugged back to 3000' w/sand + 45 sx cement dumped w/bailer. Shot casing @ 1500'-990'-735'. Pulled 735' casing. Pumped 350 sx cement w/35 sx Hulls down casing @ 400# max. Shut in @200#.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Petroleum Management, Inc. License No. 731  
 Address 400 N. Woodlawn, Suite 201, Wichita, KS 67208

STATE OF Kansas COUNTY OF Sedgwick, ss.

Steven P. O'Neill (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: that I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]  
Steven P. O'Neill

(Address) 400 N. Woodlawn, Suite 201  
Wichita, KS 67208

SUBSCRIBED AND SWORN TO before me this 16th day of Sept., 19 88



[Signature]  
 Notary Public

Expires: 12/21/91

DRILLERS LOG

No. 1 Schneider "B"

CASING RECORD:

3 5/8" @ 208'  
w/145 sx cement  
  
4 1/2" @ 3375'  
w/250 sx cement

TOTAL DEPTH: 3380'

COMPANY: Petroleum Management, Inc.

CONTRACTOR: Red Tiger Drilling Co.

COMMENCED: March 16, 1972

COMPLETED: March 22, 1972

DESCRIPTION:

SE SW SE  
19-4S-19W  
Phillips County,  
Kansas

ELEVATION:

FORMATION

FROM

TO

REMARKS

Shale	0	760
Sand, Hard Sand, Shale	760	1225
Shale	1225	1474
Anhydrite	1474	1510
Shale	1510	2265
Shale & Lime	2265	3020
Lime	3020	3380

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY


*Jim Farrice*  
Jim Farrice

RECEIVED  
STATE CORPORATION COMMISSION

Subscribed and sworn to before me this 23rd day of March, 1972.

MAY 25 1988

*Virginia K. Albert*  
Notary Public  
CONSERVATION DIVISION  
Wichita, Kansas



My Commission Expires:

7-23-74