

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-147-20,507-00-00

LEASE NAME MORGAN

WELL NUMBER 2

4447' Ft. from S Section Line

4471' Ft. from E Section Line

SEC. 15 TWP. 4 S RGE. 19 ~~KRXXX~~(W)

COUNTY PHILLIPS

Date Well Completed 9-3-88

Plugging Commenced 12-22-88

Plugging Completed 12-22-88

TYPE OR PRINT

NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR AMERICAN PETROLEUM COMPANY, INC.

ADDRESS 3500 N. ROCK ROAD, BLDG. 1300 WICHITA, KS.

67226

PHONE#( 310 636-5273 OPERATORS LICENSE NO. 5923

Character of Well OIL DA KCC ap

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on DECEMBER 1, 1988 & DECEMBER 21, 1988 (date)

by SHARI FEIST & DALE BALTHAZOR (HAYS DISTRICT) (KCC District Agent's Name).

Is ACO-1 filed? YES If not, is well log attached? TO ACO-1 & CP-1

Producing Formation LKC & TORONTO Depth to Top 3258' Bottom 3473' T.D. 3500'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	SURFACE	0'	218'	8 5/8"	218'	0'
	PRODUCTION	0'	3498'	5 1/2"	3498'	1560'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from    feet to    feet each set.  
PLUGGED BACK TO 3180' WITH SAND & 5 SACKS OF CEMENT ON TOP.  
3180' TO SURFACE WITH 300 SACKS OF 60/40 POZMIX, 6% GEL. AND 500# HULLS.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor PLAINS INC. License   

Address P. O. BOX 346 NESS CITY, KANSAS 67560

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: AMERICAN PETROLEUM COMPANY, INC.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

AMERICAN PETROLEUM COMPANY, INC. (Employee of Operator) of    (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well, as filed that the same are true and correct, so help me God.

(Signature) James D. Dawes

(Address) 3500 N. ROCK ROAD, BLDG. 1300  
WICHITA, KS. 67226

SUBSCRIBED AND SWORN TO before me this 23RD. day of DECEMBER, 19 88

My Commission Expires: May 3, 1990 Notary Public

  
MARCIA L. ALTERMAN  
State of Kansas  
My Appt. Exp. May 3, 1990  
CP-4  
05-88

RECEIVED  
STATE CORPORATION COMMISSION  
UCC 20 1988  
12-29-1988  
CONSERVATION DIVISION  
Wichita, Kansas

EMPHASIS OIL OPERATIONS

P. O. BOX 506

RUSSELL, KS 67665

15-147-30507-00-00

DRILLERS LOG

OPERATOR: American Petroleum Co., Inc.  
3500 N. Rock Rd., #1300  
Wichita, Kansas 67226

CONTRACTOR: Emphasis Oil Operations  
Box 506  
Russell, KS 67665

LEASE: Morgan

WELL #2

LOCATION: Approx. SE NW NW  
Section 15- 4S-19W  
Phillips County, Kansas

LOGGERS TOTAL DEPTH: 3500'

ROTARY TOTAL DEPTH: 3499'

COMMENCED: 8/29/88

CASING: 8-5/8" @ 218' w/125 sks cement  
5-1/2" @ 3498' w/100 sks cement

ELEVATION: 2076' K.B.

COMPLETED: 9/3/88

STATUS: Oil Well

RECEIVED  
STATE CORPORATION COMMISSION

DEC 20 1988

CONSERVATION DIVISION  
Wichita, Kansas


DEPTHS & FORMATIONS

(All measurements from K.B.)

Top Soil, Sand & Clay	85'	Red Bed	1900'
Shale	643'	Shale	3009'
Dakota Sand	810'	Top of Topeka	3010'
Red Bed	870'	Top of Heebner	3211'
Cedar Hills Sand	1062'	Top of Lansing-Kansas City	3256'
Red Bed	1574'	R.T.D.	3499'
Anhydrite	1600'		


STATE OF KANSAS )  
                          ) ss  
COUNTY OF RUSSELL)


Kyle B. Branum, of Emphasis Oil Operations, states that the above and foregoing is a true and correct log of the above captioned well, to the best of his knowledge.

  
Kyle B. Branum

Subscribed and sworn to before me on September 7, 1988.

My commission expires: February 6, 1992.



  
Glenda R. Tiffin, Notary Public