

15-147 00634-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Phillips County. Sec. 16 Twp. 4 Rge. 19 (E) (W) X
Location as "NE/CNW/SW" or footage from lines SW SW SW
Lease Owner Leo J. Dreiling Oil Company
Lease Name Boyd Well No. 1
Office Address Victoria, Kansas 67671
Character of Well (completed as Oil, Gas or Dry Hole) D. & A.
Date well completed 8/15/64 19
Application for plugging filed 8/15/64 19
Application for plugging approved 8/15/64 19
Plugging commenced 8/15/64 19
Plugging completed 8/15/64 19
Reason for abandonment of well or producing formation -0-

If a producing well is abandoned, date of last production -0- 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation -0- Depth to top -0- Bottom -0- Total Depth of Well 3561' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Pipe				8 5/8"	184'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with rotary mud to a depth of 540' were 1st plug was set using 20 sacks of cement, 2nd plug was set at 180' using 20 sacks cement, 3rd plug was set at 40' using 10 sacks cement and filling hole to surface.

RECEIVED
STATE CORPORATION COMMISSION

SEP 2 1964
09-02-1964
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor L. J. Dreiling & Sons, Inc.
Address Victoria, Kansas

STATE OF Kansas, COUNTY OF Ellis, ss.
I, Leo F. Dreiling a partner of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leo F. Dreiling
LEO F. DREILING

SUBSCRIBED AND SWORN to before me this 17th day of August, 19 64

My commission expires August 14, 1965
Ronald Zimmerman Notary Public.

L. J. DREILING and SONS, Inc.

VICTORIA, KANSAS

15-147-00634-00-00

WELL LOG

Company Leo J. Dreiling Oil Company
Victoria, Kansas

Sec. 16 Twp. 4 Rng. 19

Farm Boyd No. 1

Location SW SW SW

Total Depth 3561'

County Phillips County, Kansas

Comm. 8/8/64 Comp. 8/15/64

Elevation: D. F. 1997'

Contractor L. J. DREILING & SONS, INC.
VICTORIA, KANSAS

G. R.

Casing Record

Cement Record

Production:

8 5/8" - - - 18 1/2'

125 sacks cement

D. & A.

Figures Indicate Bottom of Formations

0 - 50	Surface Clay
50 - 90	Sand & Clay
90 - 184	Blue Shale
184 - 623	Shale & Shells
623 - 1150	Shale
1150 - 1273	Sand
1273 - 1544	Shale & Red Bed
1544 - 1570	Anhydrite
1570 - 2010	Shale
2010 - 2269	Shale & Lime
2269 - 2463	Shale & Lime
2463 - 2634	Shale & Shells
2634 - 2866	Lime & Shale
2866 - 2973	Lime & Shale
2973 - 3089	Lime & Shale
3089 - 3174	Lime
3174 - 3221	Lime
3221 - 3262	Lime
3262 - 3285	Lime
3285 - 3291	Lime
3291 - 3357	Lime
3357 - 3448	Lime
3448 - 3496	Lime
3496 - 3557	Lime
3557 - 3561	Lime
3561	TD

RECEIVED
STATE CORPORATION COMMISSION

SEP 2 1964

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
COUNTY OF ELLIS) ss.

I, Leo F. Dreiling, of the L. J. Dreiling & Sons, Inc.,
upon oath states that the above and foregoing is a true and
correct copy from the Daily Drilling Report from your Boyd No. 1.

Leo F. Dreiling
LEO F. DREILING

Subscribed and sworn to before me this 17th day of August, 1964

Ronald Zimmerman
NOTARY PUBLIC

My Commission Expires: August 14, 1965