


15-147-00165-00-00
WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Phillips County, Sec. 20 Twp. 4S Rge. 19 (E) (W) X

Location as "NE/CNW/SW" or footage from lines SW NW SW
Lease Owner Braden - Deem, Inc.
Lease Name Kinter Well No. 1
Office Address Suite 520, 200 East First, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed 6-30-70 19____
Application for plugging approved 7-1-70 19____
Plugging commenced 7-11-70 19____
Plugging completed 7-22-70 19____
Reason for abandonment of well or producing formation _____



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo F. Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3355 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	RECEIVED STATE CORPORATION COMMISSION 07-30-1970 JUL 30 1970 CONSERVATION DIVISION Wichita, Kansas			8 5/8	134	None
				5 1/2	3354	1954.92

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Moved to location.
Moved in cleaning collar. Sanded to 2990' and dumped 5 sacks of cement.
Loaded hole with water. 10 hrs.
R igged up jacks. Changed head. Worked pipe. Shot pipe at 2554'. Started pipe. Well flowed while pulling 17 joints of pipe. Pipe hung up at 2000'.
Worked 1 joint of pipe out. 10 hrs.
Pulled pipe. 3 hrs. No Charge
Worked and pulled 8 more joints of pipe. 6 hrs.
Pulling pipe. 2 hrs. No Charge
Worked pipe. Broke circulation and spotted 35 bbls. of oil. 10 hrs.
Worked pipe, still not loose 3 hrs.
Worked pipe. Moved pipe 4 feet. Shot pipe at 1700' (2 joints up). 10 hrs.
Worked pipe. Pumped 80 bbls. water down the annulus, and 40 bbls. water down the 5 1/2" casing. Shot pipe at 1600', 1500', 1350', 1253', and 1150'. 8 hrs.
Pulled 17 joints of casing 2 hrs. No Charge
Cleaned oil off equipment. Finished pulling a total of 63 joints of casing. 4 hrs. No Charge
Loaded unit and moved off location. 2 hrs.
Squeezed well with 2 sacks of hulls, 20 sacks of mud and 120 sacks of pozmix cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling Company, Inc.
Address P. O. Box 221 Great Bend, Kansas 67530

STATE OF Kansas, COUNTY OF Barton, ss.
James W. Rockhold (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold
P. O. Box 221 Great Bend, Kansas
(Address)

Subscribed and sworn to before me this 28 day of July, 19 70
Alice Michell
Notary Public.

My commission expires May 27, 1973
BARTON COUNTY, KANSAS

JUL 1 1970

CONSERVATION DIVISION
Wichita, Kansas

07-01-1970

ROTARY DRILLING LOG

15-147-00165-00-00

OPERATOR: The P. W. Rine Drilling Company
CONTRACTOR: D & D Drilling Company, Inc.

Comm: 12-9-63
Comp: 12-18-63

WELL: Kinter #1
Location: SE 1/4 SW 1/4 Sec. 20-4S-19W
County: Phillips County, Kansas

Formations:

Remarks:

Shale & Rock 134'
Shale & Sand 1139'
Any. 1515'
Shale 1210'
Sand & Shells 1900'
Shale 2060'
Lime & Shale 3107'
Lime 3251'

Set 4 joints of 3 5/8" casing
at 134', cemented with 150 sacks
EA-5. Cement Conc.

Rotary Total Depth 3355'

Set 106 joints of 5 1/2" casing
at 3354', cemented with 150 sacks
salt saturated Pozmix. Circulated
100 sacks thru D.V. Tool.

A F F I D A V I T

State of Kansas)
) SS
County of Sedgwick)

James R. Daniels, of lawful age, being duly and solemnly sworn on oath says: I am a resident of Wichita, Sedgwick County, Kansas, and I hereby known and on oath state, the above drilling log covering the Kinter No. 1 located in the SE 1/4 SW 1/4 of Section 20-4S-19W, Phillips County, Kansas is true and correct to the best of my knowledge and belief. Further affiant saith not.

D & D Drilling Company, Inc.

By: James R. Daniels
James R. Daniels

Subscribed and sworn to before me this 23rd day of December, 1963.

My Commission Expires 11-13-66

Colleen Chapple - Notary Public