

15-147-30016-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

OR

FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging of formations.

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Phillips County. Sec 20 Twp. 4S Rge. (E) 19 (W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines. SW NW NW

Lease Owner. Helmerich & Payne, Inc.

Lease Name. Kinter

Well No. 1

Office Address. 415 Philtower Building, Tulsa 3, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed. 4-28- 1946

Application for plugging filed. 4-29- 1946

Application for plugging approved. 4-29- 1946

Plugging commenced. 4-29- 1946

Plugging completed. 4-30- 1946

Reason for abandonment of well or producing formation. Dry hole

If a producing well is abandoned, date of last production. 19

Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well. Mr. Kerr

Producing formation. None Depth to top. Bottom. Total Depth of Well. 3832' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				10-3/4"	160'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 150', bridged with rock and dumped 15 sacks of cement. Mudded hole to 20', bridged with rock and dumped 10 sacks of cement to surface.

PLUGGING
MAY 20 4 1946
53 LINE 12

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to. Helmerich & Payne, Inc.
Address. 415 Philtower Building, Tulsa 3, Oklahoma

MAY 5 1946
05-07-1946

STATE OF OKLAHOMA, COUNTY OF TULSA, SS.

Charles F. King, Chief Production Clerk, (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Charles F. King

415 Philtower Bldg., Tulsa 3, Oklahoma
(Address)

SUBSCRIBED AND SWORN to before me this 3rd day of May 1946

Notary Public

My commission expires 7-22-47

Kinter #1
SW/4 NW/4 NW/4 of Section 20-13-19N,
Phillips County, Kansas
Helmerich & Payne, Inc.

15-147-30016-00-00

Commenced: April 13, 1946
 Completed: April 30, 1946


Surface dirt	0	30
Sand and lime shells	30	150
Shale	160	450
Shale and shells	450	640
Sand	640	700
Shale	700	830
Shale and sand streaks	830	940
Shale and shells	940	1015
Sand and lime	1015	1080
Shale	1080	1200
Red shale	1200	1340
Red shale	1340	1345
Sandy shale and red bed	1345	1490
Anhydrite	1490	1550
Shale and shells	1550	2080
Lime	2080	2115
Shale and shells	2115	2150
Lime and shale	2150	2160
Lime and shells	2160	2210
Shale and shells	2210	2305
Lime and shale streaks	2305	2445
Lime and shale	2445	2680
Lime	2680	2700
Lime and shale	2700	3000
Shale	3000	3080
Lime (broken)	3080	3086
Lime and shale	3086	3170
Hard cherty lime and iron pyrite	3170	3186
Lime and shale streaks	3186	3215
Lime and shale	3215	3230
Lime	3230	3235
Lime and shale	3235	3235
Lime (cherty)	3235	3260
Lime	3260	3292
Lime and shale	3292	3341
Lime	3341	3395
Lime and shale	3395	3438
Lime and shale	3438	3438
Arbuckle Lime	3438	3512
Lime	3512	3727
Lime	3727	3795
Reagan sand	3795	3832
TOTAL DEPTH	3832	

PLUGGING RECORD

PLUGGING

FILE NO. 20 4 R194

BOOK PAGE 53 LINE 12



Set plug at 108' and cemented with 15 sacks.

Set top plug at 15' from bottom of cellar and cemented with 10 sacks of cement up to bottom of cellar.

STATE OF OKLAHOMA)
 COUNTY OF TULSA)

I hereby affirm that the above and foregoing is a true and correct copy of the log of the Kinter Well #1, located in the Southwest Quarter of the Northwest Quarter of the Northwest Quarter of Section 20, Township 4 South, Range 19 West, Phillips County, Kansas.

HELMERICH & PAYNE, INC.
 By William Cross Hurst
 Treasurer

Subscribed and sworn to before me, a Notary Public, this 8th day of May, 1946.

Paul Griffin
 Notary Public

My commission expires July 22, 1947