


15-137-00049-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Norton County, Sec. 28 Twp. 4S Rge. (E) 22 (W)
Location as "NE/CNW 1/4 SW 1/4" or footage from lines NW 1/4 SW 1/4 SE 1/4
Lease Owner Rex & Morris Drilling Company
Lease Name Weathers Well No. 1
Office Address El Dorado, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed September 19 1950
Application for plugging filed September 19 1950
Application for plugging approved September 19 1950
Plugging commenced September 19 1950
Plugging completed September 19 1950
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19 --
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas
Producing formation Depth to top Bottom Total Depth of Well 3807 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Surface Casing				8 5/8"	205'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud from 3807 feet to 200 feet. Set wood plug at 200 feet and filled with 1 sack of hulls, 2 sacks of dry cement and 13 sacks of mixed cement to 150 feet. Filled casing with heavy mud from 150 feet to 40 feet. Set wooden plug at 40 feet and filled with 10 sacks of cement to bottom of cellar.

RECEIVED
STATE CORPORATION COMMISSION
OCT 18 1950
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Rex and Morris Drilling Company
Address P. O. Box 334, El Dorado, Kansas 10-18-50

STATE OF Kansas, COUNTY OF Butler, ss.
J. E. Morris (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. E. Morris
El Dorado, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 17th day of October, 1950.

Martin J. Chestasi
Notary Public.

My commission expires June 29, 1953.

PLUGGING
FILE DEC 28 4 22
BOOK PAGE 30 LINE 1

15-137-00049-00-00

REX AND MORRIS DRILLING COMPANY

LOG OF WEATHERS WELL NO. 1

NW 1/4 SW 1/4 SE 1/4 SECTION 28-48-22W, NORTON COUNTY, KANSAS

DATE COMMENCED: September 8, 1950

DATE COMPLETED: September 19, 1950

<u>Formation</u>	<u>From</u>	<u>To</u>	<u>Remarks</u>
Surface Clay	0	20	
Sand	20	30	
Shale	30	70	
Sand	70	80	
Clay	80	130	
Sand	130	140	
Clay	140	180	
Shale	180	620	Set 8 5/8" Surface Pipe at 205 feet. Cemented with 125 Sacks of Cement.
Shale, Shells and Sand	620	1385	
Sand	1385	1420	
Shale and Shells	1420	1450	
Sand	1450	1675	
Shale and Shells	1675	1927	
Anhydrite	1927	1950	
Shale and Shells	1950	2440	
Lime and Shale	2440	3280	
Lime	3280	3580	
Shale and Sandy Lime	3580	3590	
Lime	3590	3602	
Shale and Lime	3602	3632	
Lime	3632	3666	
Sand and Shale	3666	3687	
Lime and Shale	3687	3720	
Sand, Lime and Shale	3720	3765	
Lime	3765	3790	
Shale and Lime	3790	3797	
Granite Wash	3797	3807	
Total Depth		3807	Dry and Abandoned.

Certificate

I, W. R. Hunter, Vice-President of Barnett Drilling, Inc., hereby certify that, to the best of my knowledge and belief, the above is a true and correct log of the Weathers Well No. 1, located in the NW 1/4 SW 1/4 SE 1/4 of Section 28-48-22W, Norton County, Kansas.

W. R. Hunter

Subscribed and sworn to before me in and for the County of Sedgwick, State of Kansas, this 12th day of October, 1950.

Delaine Oliver
Notary Public.

My commission expires May 12, 1951.

RECEIVED
STATE CORPORATION COMMISSION
OCT 18 1950
CONSERVATION DIVISION
Wichita, Kansas

10-18-50

PLUGGING
FILE SEC 28-48-22W
BOOK PAGE 30 LINE 1