

15-137-00267-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

WELL PLUGGING RECORD

Norton County. Sec. 8 Twp. 4S Rge. (E) 22(W)

Location as "NE/CNW/SW" or footage from lines NE NE SW

Lease Owner Continental Oil Company

Lease Name Robert W. Hemphill Jr. Well No. 1

Office Address Drawer 98, Plainville, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 3-12 19 62

Application for plugging filed 3-13 19 62

Application for plugging approved (Verbal) 3-12 19 62

Plugging commenced 3-12 19 62

Plugging completed 3-12 19 62

Reason for abandonment of well or producing formation No commercial zones encountered.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty

Producing formation none Depth to top Bottom Total Depth of Well 3903 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	271'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded up to 550 feet and spotted 20 sacks at 550 feet, plugging back to 480 feet. Mudded up to 240 feet and spotted 20 sacks of cement, plugging back to 170 feet. Mudded up to 35 feet and dumped 10 sacks of cement, filling hole to surface.

RECEIVED  
STATE CORPORATION COMMISSION

MAR 15 1962

CONSERVATION DIVISION  
Wichita, Kansas

3-15-62

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Earl F. Wakefield  
Address Wichita, Kansas

STATE OF Kansas, COUNTY OF Rooks, ss. L. E. Powell (employee of owner) or (owner/operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

ARC (Signature) L. E. Powell  
State CRW File Drawer 98  
Plainville, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 13th day of March 19 62

My commission expires 12-2-65 Kenneth J. Querry Notary Public.

LEASE: R. W. HEMPHILL, JR. #1  
OPERATOR: CONTINENTAL OIL CO.  
CONTRACTOR: EARL F. WAKEFIELD  
COMM: 3-3-62 COMP: 3-12-62

LOCATION: NE NE SW  
SECTION 8-4S-22W  
NORTON COUNTY, KANSAS  
CASING: 8 5/8" Set at 271'

Surface Soil	40
Sand and Clay	100
Shale	275
Shale and Red Bed	659
Shale and Sand	815
Sand	1250
Sand and Shale and Shells	1635
Shale, Lime, Sand and Anhydrite	2039
Anhydrite	2046
Shale and Lime	2540
Shale, Lime and pyrite	2677
Lime	2800
Lime and Shale	2920
Shale and Lime	3003
Lime	3225
Lime with Shale	3325
Lime	3577
Lime and Chert	3623
Lime and Shale	3903
T.D.	3903

**RECEIVED**  
STATE CORPORATION COMMISSION  
APR 20 1962  
CONSERVATION DIVISION  
Wichita, Kansas  
4-20-62

STATE OF KANSAS )  
                          ) ss  
COUNTY OF SEDGWICK )

I hereby certify that the above is a true and correct copy of the log on the R. W. HEMPHILL, JR. NO. 1 well, located NE NE SW of Section 8-4S-22W, Norton County, Kansas.

EARL F. WAKEFIELD  
By Fred S. Eisher

Subscribed and sworn before me this 22nd day of March, 1962.

My commission expires:  
January 25, 1965

Wanda M. Riley  
NOTARY

*State Corp Comm  
Kansas Geological Society  
CPW*