

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
REV. 03/92
RECEIVED
KANSAS CORPORATION COMMISSION
SEP 01 1994
9-1-94
CONSERVATION DIVISION
WICHITA, KS

15-147-00950-00-00

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 8-15-60 (Identifier number of this well). This well is listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR OXY USA INC. KCC LICENSE # 5447 ^{6/95}
(owner/company name) (operator's)

ADDRESS 110 S. Main #800 CITY Wichita

STATE Kansas ZIP CODE 67202 CONTACT PHONE # (316) 265-5624

LEASE Slinker Unit WELL# 204 SEC. 25 T. 4S R. 20 (~~East~~ **West**)

C - E/2 - NW - SE SPOT LOCATION/QQQQ COUNTY Phillips

1980 FEET (in exact footage) FROM S (circle one) LINE OF SECTION (**NOT Lease Line**)

330 FEET (in exact footage) FROM E (circle one) LINE OF SECTION (**NOT Lease Line**)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8-5/8" SET AT 157' CEMENTED WITH 125 SACKS

PRODUCTION CASING SIZE 5-1/2" SET AT 3270' CEMENTED WITH 150 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: Perfs 3135-3211'

ELEVATION 1964' / 1969' T.D. 3486' PBSD 3234' ANHYDRITE DEPTH 1518-1580'
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING As per KCC requirements.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? No

If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

J. D. Hininger PHONE# (913) 434-7681

ADDRESS Drawer D City/State Plainville, KS 67663

PLUGGING CONTRACTOR J. W. Gibson Well Service KCC LICENSE # 5866 ^{8/94}
(company name) (contractor's)

ADDRESS 505 W. Commercial, Logan, KS, 67646 PHONE # (913) 689-7573

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) 9-14-94

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 8-31-94 AUTHORIZED OPERATOR/AGENT: Carla J. Davis *Carla J. Davis*
(signature)

4)

15-147-00950-00-00

R. W. Rine Drilling Company
Wichita, Kansas

Tulsa, Oklahoma
August 26, 1960

Contractor: Stickle Drilling Company
Date Commenced: August 7, 1960
Date Completed: August 15, 1960

Slinker Well No. 4,
E/2 NE SE 25-4S-20W.,
Phillips Co., Kansas

DRILLER'S LOG

DEPTH FIGURES INDICATE BASE OF FORMATION:

Surface clay & shells	159
Shale	575
Sand and shale	1015
Sand	1225
Sand & shale	1488
Anhydrite	1518
Shale	1580
Shale & shells	2510
Shale & Lime	2875
Lime & shale	3095
Lime	3130
Lime & shale	3140
Lime	3486 TD

RECEIVED
KANSAS CORPORATION COMMISSION
SEP 07 1964
9-1-64
CONSERVATION DIVISION
WICHITA, KS

I, Fred E. Stickle, hereby certify the above to be a true and complete Driller's Log of Rine Drilling Company's Slinker Well No. 4, East Half of Northeast Quarter of Southeast Quarter of Section 25-4S-20W., Phillips County, Kansas.

Fred E. Stickle
Fred E. Stickle

Edith A. Lawrence
Notary Public

My commission expires March 24, 1964

THE R W RINE DRILLING CO
WELL COMPLETION REPORT

15-147-00950-00-00

TOPS	DEPTH	DATUM
Anhydrite	1488	+481
Topeka	2920	-951
Heebner	3089	-1120
Toronto	3116	-1147
Lansing-KC	3133	-1164
Base KC	3346	-1377
Base Marnaton	3420	-1451
Penn. Cgl. sd.	3431	-1462
Eros. Arb.	3460	-1491
Arbuckle	3479	-1510
TD	3486	-1517

LEASE Slinker WELL NO. KANSAS CORPORATION COMMISSION
 LOCATION CR/ NE SE
 SEC 25 TWP 4S RGE 20W
 COUNTY Phillips STATE Kansas
 OPERATOR The R. W. Rine GEOLOGIST Paul Warner
 ELEVATION: GR 1964' OF 1966' KE 1969'

RECEIVED
 SEP 01 1994
 CONSERVATION DIVISION
 WICHITA, KS
 9-1-94

DRILLING ZERO TO PERMANENT MARKER K.B. 8.15' above Bradenhead

JOB - TOOLS	STARTED	COMPLETE	FROM	TO	REMARKS
DRILLING - Rotary	8/8/60	8/15/60	0'	157'	
COMPLETION - Cable	8/19/60	8/25/60			
WORKOVER -					Perforating, squeezing,
WORKOVER -					re-perforating, acidizing,
WORKOVER -					swabbing.
WORKOVER -					
WORKOVER -					
WORKOVER -					
WORKOVER -					

INITIAL POTENTIAL 91 BOPD WELL FLOWING FROM TO PUMPING FROM 3133 TO 3135
2% water

SIZE	WT	THUS	TYPE	GRADE	DEPTH	REMARKS	TOP cement
8-5/8"	24#	8rd	J-55	A	157'	125 sx. Pozmix / 6 sx HA5 circ.	
5-1/2"	14#	8rd		B	3270'	150 sx. Pozmix; DV 81496	2410'
2-7/8" OD	6.5#	8rd	H-40	A	236'	6/100 BO, 100 sx Howcogal	
2-7/8" OD	6.5#	8rd	J-55	B	186'		
2-7/8" OD	6.5#	8rd	J-55	C	2831'		

DATE	FROM	TO	NO SHOTS	RESULTS
8/20/60	3133	3135	6 "A-2"	1 1/2 BflPH (10% wtr) "Top" zone.
8/24/60	3133	3135	6 "E"	6 gal. fluid/hr. (all wtr. to 90% oil in 3-3/4 hrs.)

DATE	FROM	TO	GALLONS	RESULTS
8/21/60	3133	3135	250 mud A.	Swb. 17-20 B fl. PH (75% wtr.) Squeezed
8/24/60	3133	3135	250 XF 33W-17	50# max. Swb. 7 1/2 B fl./hr. (5% wtr.)

15-147-00950-00-00



15-147-00950-00-00

Kansas Corporation Commission

Joan Finney, Governor Susan M. Seltsam, Chair F.S. Jack Alexander, Commissioner Rachel C. Lipman, Commissioner
Judith McConnell, Executive Director Brian Moline, General Counsel

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

September 2, 1994

OXY USA Inc
110 S Main #800
Wichita KS 67202

Slinker Unit #204
API 15-N/A
1980 FSL 330 FEL
Sec. 25-04S-20W
Phillips County

Dear J. D. Hininger,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well..


Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,


David P. Williams
Production Supervisor

District: #4
2301 E 13th
Hays KS 67601
(913) 628-1200

William R. Bryson, Director Conservation Division
KCC, Conservation Division, Wichita State Office Building
130 S. Market, Room 2078, Wichita, Kansas 67202 (316) 337-6200